

QUALLA/WHITTIER PARK - Bid Tab



PARK						
ITEM	SITE GRADING & PREPARATION	REFERENCE	QUANTITY	UNIT	UNIT COST	TOTAL COST
1	MOBILIZATION		1	LS		\$0.00
2	CLEARING & GRUBBING, BRIAR REMOVAL (APPROX 2.0 AC)		1	LS		\$0.00
3	DEMO AND HAUL OFF (STRUCTURES AND DEBRIS, DILAPIDATED BUILDINGS)	L2.0	1	LS		\$0.00
4	EARTHWORK (ROUGH GRADING, EXCAVATION AND HAUL OFF) *100% CUT TAKEN OFF SITE (8400 CUBIC YARDS CUT 8400 CUBIC YARD FILL)		16,800	CY		\$0.00
5	PROTECTION EXISTING TREES		1	LS		\$0.00
6	FINE GRADING		8,265	SY		\$0.00
7	PAVEMENT SUBGRADE STABILIZATION		1,386	SY		\$0.00
8	BUILDING SUBGRADE STABILIZATION		24	SY		\$0.00
ITEM	EROSION CONTROL					
9	INLET PROTECTION	1/EC2.0	10	EA		\$0.00
10	OUTLET PROTECTION (ENERGY DISSIPATER)	6/EC2.0	6	EA		\$0.00
11	CONSTRUCTION ENTRANCE	2/EC2.0	1	EA		\$0.00
12	CONCRETE WASHOUT	3/EC2.0	1	EA		\$0.00
13	REINFORCED SILT FENCE	7/EC2.0	1,755	LF		\$0.00
14	EROSION CONTROL MATTING (100% BIODEGRADABLE, NORTH AMERICAN GREEN)	4/EC2.0	46,365	SF		\$0.00
15	ROCK CHECK DAMS (TEMPORARY)	2/EC2.1	68	EA		\$0.00
16	SPILLWAY/SEDIMENT TRAPS WITH SKIMMER	1/EC2.2	3	EA		\$0.00
17	SEDIMENT SOCK	1/EC2.1	26	EA		\$0.00
18	TEMPORARY DIVERSION DITCH	5/EC2.0	690	LF		\$0.00
19	TEMPORARY SEEDING (INCLUDES STRAW)	4/EC2.1	4.28	AC		\$0.00
20	SURFACE ROUGHENING	3/EC2.1	1.25	AC		\$0.00
	Sub Total					\$0.00
ITEM	PAVING & CIRCULATION	REFERENCE	QUANTITY	UNIT		
21	PEDESTRIAN CONCRETE PAVING (CP1)- FIBER REINFORCED, 6" THICKNESS, 2" CABG	3/L8.0	1,262	SY		\$0.00
22	VEHICULAR CONCRETE PAVING (CP2) - 8" THICKNESS, 8" CABG	4/L8.0	124	SY		\$0.00
23	ASPHALT PAVING PEDESTRIAN (AP1) - 2" THICKNESS, 8" CABG	1/L8.0	478	SY		\$0.00
24	ASPHALT PAVING VEHICULAR (AP2) - 4" THICKNESS, 10" CABG	2/L8.0	2,864	SY		\$0.00
25	NATURAL SURFACE TRAIL (NST)	1/L8.1	2,285	LF		\$0.00
26	NATURAL SURFACE TRAIL - REINFORCED	10/L8.0	23	SY		\$0.00
27	SPLIT-RAIL FENCE	7/L8.2	11	LF		\$0.00
28	TIMBER STAIRS	1/L8.2	2	EA		\$0.00
29	CONCRETE STAIRS	8/L8.2	18	SY		\$0.00
30	GRAVEL VERGE, 2" WIDE, 2" STONE / 8" THICK, COMPACTED IN 2" LIFTS 95% PROCTOR OR GREATER	6/L8.0	17	SY		\$0.00
31	VEHICULAR GUARDRAIL	6/L8.2	197	LF		\$0.00
32	WHEEL STOPS, 6' LONG	5/L8.4	24	EA		\$0.00
33	PAINTING AND STRIPING (PARKING SPACES, ARROW STRIPING, STOP BARS, CROSSWALKS)	L1.0;7;8/L8.4	1	LS		\$0.00
34	6" CONCRETE CURB	9/L8.0	172	LF		\$0.00
35	FLUSH CONCRETE CURB	8/L8.0	246	LF		\$0.00
36	HANDRAIL	5/L8.2	57	LF		\$0.00
37	ACCESSIBLE RAMP	1/L8.4	6	SY		\$0.00
38	DETECTABLE WARNING PLATE	2/L8.4	2	EA		\$0.00
	Sub Total					\$0.00
ITEM	SITE ELEMENTS	REFERENCE	QUANTITY	UNIT		
	WALLS					
39	HEADWALL	1/L8.5	1	EA		\$0.00
40	STONE SEAT WALL	2/L8.2	26	LF		\$0.00
41	SEGMENTAL BLOCK RETAINING WALL	SPECIFICATION	155	LF		\$0.00
42	BOULDER RETAINING WALL	3/L8.2	83	LF		\$0.00
	PLAYGROUNDS					
43	PLAYGROUND STRUCTURES	SPECIFICATION	1	LS		\$0.00
44	PLAY SURFACE - POUR IN PLACE (PS)	5/L8.0	1	LS		\$0.00
45	UNDERDRAIN (FABRIC AROUND THE PIPE SECTION)	5/L8.5	197	LF		\$0.00
46	BOULDER SCRAMBLE	5/L8.3	1	LS		\$0.00
47	BOULDER LANDSCAPE STEPS	4/L8.2	1	LS		\$0.00

48	CULVERT SLIDE	1/L8.3	29	LF	\$0.00
49	CLIMBING LOGS	3/L8.3	1	LS	\$0.00
50	STEPPING STUMPS	2/L8.3	1	LS	\$0.00
51	PLAYGROUND MULCH	7/L8.0	176	SF	\$0.00
52	WATER FOUNTAIN	SPECIFICATION	1	EA	\$0.00
53	EMBANKMENT SLIDE	SPECIFICATION	1	EA	\$0.00
FURNISHINGS					
54	BENCH SWING	4/L8.3	3	EA	\$0.00
55	BENCH	SPECIFICATION	9	EA	\$0.00
56	PICNIC TABLE - UNIVERSAL ACCESS	SPECIFICATION	9	EA	\$0.00
57	PICNIC TABLE - 6', RECYCLED PLASTIC LUMBER	SPECIFICATION	10	EA	\$0.00
SIGNAGE					
58	PARK SIGN	2/L8.1	1	EA	\$0.00
59	STOP SIGN (MUTCD R1-1)	6/L8.4	1	EA	\$0.00
60	YIELD TO PEDESTRIAN (MUTCD R1-6)	6/L8.4	2	EA	\$0.00
61	ONE WAY, KEEP RIGHT (MUTCD R4-7a)	6/L8.4	1	EA	\$0.00
62	ADA MARKER	4/L8.4	3	EA	\$0.00
63	ADA SIGNAGE	3/L8.4	3	EA	\$0.00
Sub Total					\$0.00
ITEM	STRUCTURES	REFERENCE	QUANTITY	UNIT	
64	PRE-FABRICATED PAVILION	SPECIFICATION	1	LS	\$0.00
65	PRE-FABRICATED RESTROOM	SPECIFICATION	1	LS	\$0.00
Sub Total					\$0.00
ITEM	UTILITY SERVICES	REFERENCE	QUANTITY	UNIT	
66	WATER	C SHEETS	1	LS	\$0.00
67	SEWER		1	LS	\$0.00
68	ELECTRICAL		1	LS	\$0.00
Sub Total					\$0.00
ITEM	STORMWATER & DRAINAGE	REFERENCE	QUANTITY	UNIT	
69	6" PIPE, HDPE	L6 SHEETS	40	LF	\$0.00
70	15" PIPE, HDPE	L6 SHEETS	371	LF	\$0.00
71	18" PIPE, HDPE	L6 SHEETS	27	LF	\$0.00
72	24" PIPE, HDPE	L6 SHEETS	43	LF	\$0.00
73	PERMANENT SWALE CHECKS	8/L8.5	37	EA	\$0.00
74	BIORETENTION PREPARATION, INCLUDES SOIL MEDIA	4/L8.5	1144	SF	\$0.00
75	UNDERDRAIN (4" PERFORATED PIPE, WASHED 57 STONE, FILTER FABRIC)	5/L8.5	120	LF	\$0.00
76	DROP INLET CONCRETE BOX	3/L8.5	9	EA	\$0.00
77	AREA CATCHMENT BASIN, METAL GRATE TOP	N/A	2	EA	\$0.00
78	WEIR	6/L8.5	1	EA	\$0.00
79	LEVEL SPREADER	7/L8.5	3	EA	\$0.00
80	INFILTRATION TRENCH (6" DEPTH WASHED RIVER ROCK, 24" DEPTH WASHED #57 STONE WRAPPED IN FILTER FABRI	3/L8.1	85	LF	\$0.00
Sub Total					\$0.00
ITEM	PLANT	REFERENCE	QUANTITY	UNIT	
81	TREES, 10' Ht. (BALL & BURLAP)	L7 SHEETS	40	EA	\$0.00
82	TREES, 6' Ht. (BALL & BURLAP)	L7 SHEETS	17	EA	\$0.00
83	SHRUBS (10 GAL POT)	L7 SHEETS	21	EA	\$0.00
84	SHRUBS (5 GAL POT)	L7 SHEETS	101	EA	\$0.00
85	SHRUBS (3 GAL POT)	L7 SHEETS	116	EA	\$0.00
86	PLUG	L7 SHEETS	1,574	EA	\$0.00
87	PINT POT	L7 SHEETS	40	EA	\$0.00
88	#1 POT	L7 SHEETS	1,876	EA	\$0.00
89	#2 POT	L7 SHEETS	29	EA	\$0.00
90	1 GALLON POT	L7 SHEETS	287	EA	\$0.00
91	SEEDS	L7 SHEETS	3	AC	\$0.00
92	MULCH (SHREDDED HARDWOOD)	L7 SHEETS	98	CY	\$0.00
Sub Total					\$0.00
OVERALL SUBTOTAL					\$0.00
10% CONSTRUCTION CONTINGENCY					\$0.00
OVERALL TOTAL					\$0

NOTES: Quantities provided are provided as a courtesy to aid in contractor takeoffs. If discrepancies are found between quantities provided and the plans, the plan sets shall take precedence. See plan sets for specifications for items listed.

1. Comprehensive grading take-offs include all cut and fill required for project.
2. All materials and structures listed includes materials and install per plans or manufacturer's specifications (whichever is listed).
3. Responsibility if the bidder to ensure tabs are calculating correctly