
### QUALLA/WHITTIER COMMUNITY PARK

BID SET







CLIENT/OWNER: Jackson County Parks & Recreatiom 88 Cullhowee Mtn Rd

Sylva, NC 28779 (828) 293-3053



LANDSCAPE ARCHITECT:
Equinox
14 O'Henry Avenue, Suite 206
Asheville, NC 28801
(828) 253-6856 (x202)
david@equinoxenvironmental.com

PROJECT NFORMATION

ADDRESS: TR 1 Sunset Farms Road Whittier, NC 28789 Latitude: 35.426324° N Longitude: -83.324217° W

PROJECT SIZE:
Approximately 10.5 Ac Total
Disturbance area is 6.80 Ac

All aspects of work shall be performed in accordance with all applicable local, state, and federal regulations pertaining to worker safety.

### OTHER CONTACTS

PROFESSIONAL LAND SURVEYOR: WithersRavenel Marshall Wight 115 MacKenan Drive Cary, NC 27511 (919) 469-3340

ELECTRICAL & UTILITY ENGINEER: WithersRavenel Jason Bertoncino 115 MacKenan Drive Cary, NC 27511 (919) 469-3340

### SHEET INDEX

Sheet List Table						
Sheet Number	Sheet Title					
L0.0	Cover Sheet					
L0.1	Index & Notes					
L0.2	Combined Survey					
L0.2.1	Alliance Survey					
L0.2.2	WithersRavenel Survey					
L1.0	Site Plan					
L2.0	Site Preparation					
L3.0	Layout Plan					
L3.1	Layout Plan Enlargement					
L3.2	Layout Plan Enlargement					
L3.3	Layout Plan Enlargement					
L4.1	Materials Plan Enlargement					
L4.2	Materials Plan Enlargement					

EC2.0	Erosion Control Details
EC2.1	Erosion Control Details
EC2.2	Erosion Control Details
EC2.3	Erosion Control Notes
L8.0	Paving Details
L8.1	Park Sign & Trail Details
L8.2	Site Details
L8.3	Play Feature Details
L8.4	Parking & Accessibility Details
L8.5	Stormwater Details
C1.00	Utility Plan
C2.00	Electrical Plan
C3.00	Details

### Sequoyah National Golf Club Smokey Mountain Elementary School SITE WNC Church of God Assembly Grounds

VICINITY MAP

### NOTES & GENERAL SPECIFICATIONS

### **GENERAL:**

- 1. CALL 811 TO LOCATE ALL UTILITIES PRIOR TO DIGGING
- 2. SEDIMENTATION OF THE STORMWATER CONTROL MEASURES WILL CAUSE FAILURE, THEREFORE, INSTALL ALL STORMWATER CONTROL MEASURES ONLY AFTER ALL SEDIMENT AND EROSION ON—SITE IS CONTROLLED AND SITE IS STABILIZED AND SEEDED. (SEE EROSION CONTROL MEASURE SECTION IN NOTES FOR MORE DETAIL).
- 3. WHERE CONFLICTS OCCUR BETWEEN NOTES, DRAWINGS, OR SPECIFICATIONS, THE CONTRACTOR SHALL NOT PROCEED WITH THE AFFECTED WORK UNTIL THE LANDSCAPE ARCHITECT ISSUES A CLARIFICATION.

### <u>APPROVALS</u>

- 4. PRIOR TO CUTTING IN THE GREENWAY, THE CENTER LINE OF THE GREENWAY SHALL BE FLAGGED AND REVIEWED BY THE CLIENT AND THE PROJECT LANDSCAPE ARCHITECT.
- 5. PRIOR TO FINAL GRADING THE DRAINAGE IN THE PROJECT AREA SHALL BE REVIEWED BY THE CLIENT AND PROJECT LANDSCAPE ARCHITECT.

  CONSTRUCTION:
- 6. SEE CONSTRUCTION SEQUENCE ON EROSION CONTROL SHEETS.
- 7. BURNING IS NOT PERMITTED.
- 8. EDGE OF WATER AT TIME OF SURVEY SHOWN ACTUAL WATER ELEVATION MAY VARY.
- CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ALL APPLICABLE BUILDING PERMITS, LABOR, MATERIALS, AND EQUIPMENT REQUIRED TO PERFORM THE SPECIFIED WORK.
- 10. ALL ASPECTS OF WORK SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE LOCAL, STATE, AND FEDERAL REGULATIONS PERTAINING TO WORKER SAFETY.
- 11. ALL PAVING MATERIALS AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE NC DOT "STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES".
- 12. CONTRACTOR SHALL COORDINATE ALL SITE ACTIVITIES WITH OWNER OR DESIGNATED REPRESENTATIVE. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING DELIVERY, STORAGE, AND HANDLING OF ALL MATERIALS REQUIRED FOR THE PROJECT.
- 13. ALL DISTURBED AREAS SHALL BE STABILIZED WITHIN 30 WORKING DAYS FOLLOWING THE COMPLETION OF LAND DISTURBING ACTIVITIES. IF THERE ARE MORE STRINGENT SOIL STABILIZATION GUIDELINES PUT IN PLACE BY LOCAL, COUNTY, STATE, OR FEDERAL AGENCIES OR CALLED FOR BASED ON PERMIT REQUIREMENTS THEN THE MORE STRINGENT GUIDELINES SHALL CONTROL AND GOVERN ON THE PROJECT.
- 14. CONTRACTOR SHALL REMOVE AND DISPOSE OF ALL SPOIL MATERIAL OFF OF THE OWNER'S PROPERTY IN COMPLIANCE WITH ALL FEDERAL, STATE, AND LOCAL ENVIRONMENTAL LAWS AND REGULATIONS AT THE PRE—DETERMINED LANDFILL SITE. LANDFILL FEES SHALL BE INCLUDED IN THE CONTRACTOR'S PROJECT FEE. THIS INCLUDES ALL SURPLUS SOIL MATERIAL, UNSUITABLE TOPSOIL, ROCK, OBSTRUCTIONS, DEMOLISHED MATERIALS AND WASTE MATERIALS (INCLUDING TRASH AND DEBRIS). ANY BORROW SITE UTILIZED FOR BORROW MATERIAL IS REQUIRED AN APPROVED EROSION AND SEDIMENT CONTROL CERTIFICATE/PERMIT PRIOR TO THE INITIATION OF THE LAND DISTURBING ACTIVITY.
- 5. REMOVE ALL DAMAGED TREES NEAR GREENWAY, PARKING, AND TRAILHEAD THAT POSE A SAFETY HAZARD.
- 6. CONTRACTOR TO FURNISH AND PROVIDE THIRD PARTY MATERIAL TESTING AS PART OF CONSTRUCTION BID.
- 7. CONTRACTOR TO FURNISH AND PROVIDE THIRD PARTY GEOTECHNICAL EVALUATION OF SUBGRADE TO ENSURE ADEQUATE BEARING.
- 8. CONTRACTOR TO CONFORM TO OWNER'S SAFETY PROTOCOL AND PROVIDE A SITE SPECIFIC SAFETY PLAN AND OTHER DOCUMENTATION AS NECESSARY.
- 9. FOR PLASTIC SEWER PIPING, STORM AND SANITARY, AN INSULATED COPPER TRACER WIRE OR OTHER APPROVED CONDUCTOR SHALL BE INSTALLED ADJACENT TO AND OVER THE FULL LENGTH OF THE PIPING. THE TRACER WIRE SIZE SHALL BE NOT LESS THAN 14 AWG AND THE INSULATION TYPE SHALL BE LISTED FOR DIRECT BURIAL.
- 10. ALL FASTENERS TO BE GALVANIZED STEEL UNLESS OTHERWISE SPECIFIED
- 11. ALL WOOD TO BE PRESSURE TREATED UNLESS OTHERWISE SPECIFIED.
- 12. SEE SPECIFICATIONS FOR COMPOSITE TIMBER.

### GRADING:

- 13. ALL PROPOSED SPOT GRADES AND CONTOURS SHOW FINISH GRADE.
- 14. ALL CUT SLOPES AND FILL SLOPES TO BE 2:1 AND 3:1 RESPECTIVELY UNLESS OTHERWISE INDICATED.
- 15. CROSS SLOPES ON SIDEWALKS SHALL NOT EXCEED 1.9%
- 16. GROUND SURFACE SHALL BE SHAPED TO PROVIDE POSITIVE DRAINAGE. A

MIN. OF 2% IN THE DIRECTION OF DESIRED FLOW IS REQUIRED FOR NON PAVED SURFACES AND A MIN. OF 1% FOR PAVED SURFACES.

L4.3

L5.1

L5.3

L6.0

L6.1

L6.2

L6.3

L6.4

L7.1

L7.2

L7.3

L7.4

EC1.0

EC1.1

Materials Plan Enlargement

**Grading & Drainage Enlargement** 

**Grading & Drainage Enlargement** 

**Grading & Drainage Enlargement** 

Stormwater Plan

Stormwater Plan Enlargement

Stormwater Plan Enlargement

Stormwater Plan Enlargement

Delineation Map

Planting Plan Enlargement

Planting Plan Enlargement

Planting Plan Enlargement

Plant Schedule & Details

**Erosion Control Plan P1** 

Erosion Control Plan P2

- 17. ALL PROFILES REFLECT CENTERLINE GRADES.
- 18. ROAD CROSS SECTIONS ARE BASED ON PROPOSED CENTERLINES.
- 19. SAFETY RAILING TO BE APPLIED TO SIDEWALKS AND TRAILS FOR SAFETY WHEN THE FOLLOWING CONDITIONS ARE MET— THE DOWNHILL SIDE OF THE WALK EXCEEDS A 30" ELEVATION CHANGE WITHIN 36" HORIZONTAL CHANGE. (SEE NOTE 65 "SAFETY RAILING NOTES")

### GEOTECHNICAL:

- 20. IN SOME LOW, WET AREAS ON SITE, UNDERCUTTING OF EXCESSIVELY SOFT MATERIALS MAY BE CONSIDERED INSUFFICIENT. IN SUCH LOW-LYING AREAS, THE USE OF REINFORCED BIAXIAL— GEOGRID MAY BE NECESSARY UNDER THE ADVISEMENT OF THE OWNER AND THE GEOTECHNICAL ENGINEER, AS THESE FIELD CONDITIONS MAY ARISE.
- 21. IF SOFT OR UNSUITABLE SOILS SUCH AS UNDOCUMENTED FILL OR MOISTURE SENSITIVE SOILS ARE OBSERVED, AT FOOTING LOCATIONS OR LOCATIONS REQUIRING COMPACTION, THE UNSUITABLE SOILS SHOULD BE UNDERCUT AND REMOVED. ANY UNDERCUT SHOULD BE BACKFILLED WITH CRUSHED STONE, ENGINEERED FILL, OR LEAN CONCRETE UP TO THE ORIGINAL DESIGN BOTTOM OF THE FOOTING AND/OR SURFACE BASE COURSE.
- 22. PROOF ROLLING UNDER THE OBSERVATION OF A GEOTECHNICAL ENGINEER SHOULD BE CONDUCTED BEFORE THE LAYING OF ANY BASE LAYER OF PAVING.

### CONCRETE

- 23. UNLESS OTHERWISE SPECIFIED, ALL CONCRETE SHALL HAVE NATURAL SAND FINE AGGREGATE, EMBEDDED FIBERGLASS, AND NORMAL WEIGHT COARSE AGGREGATES CONFORMING TO ASTM C33, TYPE I PORTLAND CEMENT CONFORMING TO ASTM C150, AND SHALL HAVE THE FOLLOWING MINIMUM COMPRESSIVE STRENGTH (F'C) AT 28 DAYS:
- 23.1. FOOTINGS 3000 PSI W/ (ENTRAINED AIR & FLY ASH OPTIONAL)
- 23.2. SLABS 4000 PSI W/ 5% ENTRAINED AIR AND FLY ASH
- 23.3. EXTERIOR WALKS 4000 PSI W/ 5% ENTRAINED AIR AND FLY ASH
- 24. SCHEDULE OF CONCRETE FINISHES (UNLESS OTHERWISE SPECIFIED ON PLANS): SLABS: NON-SLIP STIFF BROOM FINISH.
- EXTERIOR SIDEWALKS AND PATHS: NON-SLIP STIFF BROOM FINISH.

  ALL UNEXPOSED CONCRETE SURFACES: U.O.N. ROUGH FORM FINISH.
- ALL EXPOSED CONCRETE SURFACES: U.O.N. SMOOTH RUBBED FINISH.
- 25. THE CONTRACTOR SHALL BE RESPONSIBLE FOR FURNISHING AND INSTALLING ANCHOR BOLTS, CLIPS, INSERTS, CONNECTION PLATES, SLEEVES, SLOTS, AND OTHER REQUIRED ITEMS IN ACCORDANCE WITH THE CONTRACT DRAWINGS, AND IN COOPERATION WITH OTHER TRADES PRIOR TO PLACING THE CONCRETE.
- 26. CONTROL JOINTS TO BE GROOVED WHEN CONCRETE IS STILL WET AND PLIABLE ( $\frac{1}{16}$ "  $\frac{1}{16}$ " WIDTH BY  $\frac{1}{4}$ " DEEP) WITH A MINIMUM OF EVERY 5' AND MAXIMUM OF EVERY 12' OF CONCRETE SURFACE OR PAD. FOUNDATION CONCRETE SHOULD BE PLACED THE SAME DAY AS EXCAVATION FOR FOUNDATION AND FOOTINGS.

### CONCRETE REINFORCEMENT:

27. CONCRETE REINFORCEMENT BARS SHALL CONFORM TO ASTM A615, GRADE 60. REINFORCEMENT DESIGNATED AS CONTINUOUS SHALL LAP 36 BAR DIAMETERS AT SPLICES, UNLESS NOTED OTHERWISE.

28. ALL CONCRETE REINFORCEMENT BARS SHALL BE ACCURATELY AND SECURELY

- TIED AND ANCHORED IN PLACE TO PREVENT DISLOCATION DURING THE CONCRETE PLACEMENT OPERATION.

  29. MINIMUM CONCRETE COVER PROTECTION FOR REINFORCEMENT BARS SHALL
- 29. MINIMUM CONCRETE COVER PROTECTION FOR REINFORCEMENT BARS SHALL CONFORM TO THE AMERICAN CONCRETE INSTITUTE COMMITTEE 318, SECTION 7.7, UNLESS NOTED OTHERWISE.
- SHOWN IN DETAILS.

30. WHERE REINFORCEMENT BARS ARE NOT USED, USE FIBER REINFORCEMENT AS

31. CONTRACTOR IS RESPONSIBLE FOR FURNISHING ALL TESTING AS REQUIRED DURING CONSTRUCTION, TO BE APPROVED BY THE OWNER

### STONE & ROCK:

- 32. IF EXISTING STONE AND ROCK MATERIAL ON SITE IS SUITABLE AND EQUIVALENT TO THE MATERIAL SPECIFIED, CONTRACTOR MAY UTILIZE ON SITE MATERIAL INSTEAD OF QUARRY MATERIAL WITH PRIOR APPROVAL REQUIRED BY LANDSCAPE ARCHITECT.
- 33. SAMPLES OF EACH TYPE OF ROCK, INCLUDING RIVER ROCK, BOULDERS, AND FIELDSTONE ARE TO BE APPROVED ON SITE BY LANDSCAPE ARCHITECT PRIOR TO INSTALLATION.
- 34. RIVER ROCK TO BE MIXED SIZES UNLESS OTHERWISE SPECIFIED. AVERAGE SIZE: 2"-4" (SMALL); 6"-8" (MEDIUM); AND 10"-12" (LARGE) / NOTIFY LANDSCAPE ARCHITECT IF PRODUCTS VARY FROM THIS SIZE RANGE.

- 35. ALL ROCK TO BE WASHED IMMEDIATELY BEFORE DELIVERY, UNLESS OTHERWISE SPECIFIED.
- PLANTING:

  36. CONTRACTOR SHALL VERIFY ALL QUANTITIES, MEASUREMENTS AND SITE CONDITIONS. NO PLANT SUBSTITUTIONS ALLOWED UNLESS WRITTEN PERMISSION FROM LANDSCAPE ARCHITECT IS GIVEN.
- 37. IF THERE IS A DISCREPANCY BETWEEN THE QUANTITY OF PLANTS SHOWN ON THE PLAN AND THE QUANTITIES IN THE PLANT SCHEDULE USE THE HIGHER NUMBER OF PLANTS. IF THIS OCCURS NOTIFY THE PROJECT LANDSCAPE ARCHITECT, EQUINOX.
- 38. ALL PLANTING BEDS ARE TO BE CLEANED OF ROCKS AND DEBRIS >1", TILLED TO 12" DEPTH AND AMENDED WITH 3"OF NATURES HELPER (OR APPROVED EQUAL), THEN THOROUGHLY TILLED TOGETHER. SEE STONE & ROCK.
- 39. PLANTING SOIL SHALL BE TOPSOIL AMENDED WITH 3" OF NATURES HELPER (OR APPROVED EQUAL) AND THOROUGHLY TILLED TOGETHER.
- 40. ANY REMAINING DISTURBED, NON-PLANTED AREAS ARE TO BE FINE GRADED AND SEEDED WITH FESCUE BLEND OR MULCHED AS NOTED ON PLAN.
- 41. ALL PLANTS, MATERIALS, PLANTING AND SEEDING ACTIVITIES SHALL CONFORM TO LANDSCAPE INDUSTRY STANDARDS. COMPLY WITH SIZING AND GRADING STANDARDS OF THE LATEST EDITION OF "AMERICAN STANDARD OF NURSERY STOCK". PROVIDE STOCK TRUE TO BOTANICAL NAME AND LEGIBLY TAGGED.
- 42. STOCKPILE LOCATION(S) TO BE APPROVED BY LANDSCAPE ARCHITECT.
- 43. KEEP PLANT SPECIES MOIST AND SHADED UNTIL INSTALLATION. DO NOT LEAVE IN THE SUN OR LET PLANTS DRY OUT. SATURATE PLANTS AFTER INSTALLATION. PLANTS SHALL NOT BE DELIVERED ON—SITE PRIOR TO 5 DAYS BEFORE INSTALLATION.
- 44. DIG, PACK, TRANSPORT AND HANDLE ALL PLANTS WITH CARE TO ENSURE PROTECTION FROM INJURY. STORE PLANTS IN THE MANNER NECESSARY TO ACCOMMODATE THEIR HORTICULTURAL REQUIREMENTS. HEEL—IN PLANTS IF NECESSARY TO PROTECT ROOT BALLS AND KEEP FROM DRYING OUT.
- 45. ALL PLANTS TO BE INSPECTED BY LANDSCAPE ARCHITECT PRIOR TO INSTALLATION. IF ANY PLANTS ARE IN POOR CONDITION, UNHEALTHY LOOKING, DISEASED, OR DYING THE CONTRACTOR WILL REPLACE AS REQUESTED BY LANDSCAPE ARCHITECT OR THE OWNER.
- 46. DURING INSTALLATION, THE CONTRACTOR SHALL NOTIFY LANDSCAPE ARCHITECT OF ANY CONDITIONS WHICH MAY BE HARMFUL TO PLANT LIFE, SUCH AS HAZARDOUS MATERIALS, ETC. LANDSCAPE ARCHITECT SHALL MAKE RECOMMENDATIONS TO ADDRESS THE SPECIFIC SITUATION.
- 47. CONTRACTOR TO REMOVE ALL STONES OVER 1" IN DIA. AND ALL CONSTRUCTION DEBRIS INCLUDING GRAVEL, CONCRETE, ROOTS, AND OTHER MATERIAL THAT MAY BE HARMFUL OR PREVENT PROPER ESTABLISHMENT AND OR MAINTENANCE OF PLANTING AREAS.
- 48. IN AREAS WHERE CONSTRUCTION MATERIAL IS EMBEDDED IN THE SOIL, CONTRACTOR SHALL REMOVE CONTAMINATED SOIL TO A DEPTH OF 8" AND ADD FILL WITH CLEAN, WEED-FREE PLANTING SOIL.
- LINES OR WITHIN SEWER RIGHTS-OF-WAY. CONTRACTOR SHALL CONTACT LANDSCAPE ARCHITECT TO RESOLVE ANY ISSUES BEFORE PLANTING.

  50. FOR ALL B&B TREES, ROOT BALL SHALL REMAIN MOIST AT ALL TIMES AND SHOULD RETAIN SHAPE WHEN REMOVING TOP 1/2 -2/3 OF WIRE BASKET FOR

49. LARGE MATURING TREES SHALL NOT BE PLANTED UNDER OVERHEAD POWER

- TRANSPLANTING. CONTRACTOR SHALL REMOVE TOP 1/2 OF BURLAP FROM ROOT BALL.

  51. ALL PLANTINGS TO BE WATERED AFTER PLANTING IMMEDIATELY (SAME DAY) AND TO BE CONTINUED TO BE WATERED REGULARLY (2X A DAY) UNTIL
- CONSTRUCTION IS COMPLETE .

  52. ALL CONTAINER, B&B TREES AND SHRUBS TO BE GUARANTEED FOR 1 YEAR

(MINIMUM).

- 53. ALL MULCH TO BE DOUBLE GROUND HARDWOOD MULCH, UNLESS OTHERWISE SPECIFIED.
- 54. ALL PLANTING BEDS, CONTAINER TREES AND SHRUBS, AND B&B TREES TO BE MULCHED WITH NO MORE THAN 2 ½ " OF MULCH.
  55. ALL EXISTING AND PROPOSED TREES WITHIN LIMITS OF DISTURBANCE AND NOT
- CONTAINED WITHIN A MULCHED BED ARE TO RECEIVE A 5' DIAMETER CIRCLE OF MULCH.
- 57. ALL PLANT LOCATIONS TO BE APPROVED BY EQUINOX PRIOR TO INSTALLATION.

56. AREAS UNDER EXISTING TREE DRIPLINES ARE NOT TO BE TILLED.

- 58. PLANTS TO BE PLANTED IN NATURALIZED DRIFTS, IN TRIANGULATED PATTERNS TO BLEND INTO NATURAL SETTINGS. TYPICALLY TREES AND SHRUBS CAN BE PLANTED ON 10' O.C. (ON CENTERS, TYP.) PLANTS TO BE PLANTED IN GROUPS OF 1, 3, 5, 7, 9, AND 11, TYPICAL.
- 59. PLANTINGS CAN BE A VARIETY OF TREE AND SHRUB MATERIALS, INCLUDING CONTAINERS AND BALL & BURLAP SEE PLANTING DETAILS FOR INSTALLATION PROCEDURES.

- 60. MAINTENANCE: PRUNE UP TREES FOR CLEARANCE AT 6'0" TYPICAL.
- 61. IF THERE IS A DISCREPANCY BETWEEN THE QUANTITY OF PLANTS SHOWN ON THE PLAN AND THE QUANTITIES IN THE PLANT SCHEDULE USE THE HIGHER NUMBER OF PLANTS. IF THIS OCCURS NOTIFY THE PROJECT LANDSCAPE ARCHITECT, EQUINOX.

### <u>UNIVERSAL ACCESS TRAIL GUIDELINES :</u>

- ADA ACCESS PATHS
- CLEAR TREAD WIDTH: 60 INCH MINIMUM
- CROSS SLOPE: NO MORE THAN 1.9%
- RUNNING SLOPE (TRAIL GRADE) MEETS ONE OR MORE OF THE FOLLOWING:
   -5% OR LESS FOR ANY DISTANCE.
- -UP TO 8.33% FOR 80' MAX. RESTING INTERVALS NO MORE THAN 50' APART.
- NO MORE THAN 30% OF THE TOTAL TRAIL LENGTH MAY EXCEED A RUNNING SLOPE OF 1:12.
- SIGNS: SHALL BE PROVIDED INDICATING THE LENGTH OF THE ACCESSIBLE TRAIL SEGMENT.
   THE MAXIMUM SLOPE OF A RAMP IS 1:12, THE MAXIMUM RISE FOR ANY RUN IS 30 INCHES, AND THE MINIMUM CLEAR WIDTH OF A RAMP IS 36 INCHES.
- RUN. 64. NATURAL SURFACE TRAILS:
- SEE SHEET L8.1 FOR DETAILED AND COMPREHENSIVE NOTES AND GUIDELINES.

• LEVEL LANDINGS ARE ALSO REQUIRED AT TOP AND BOTTOM OF EACH RAMP

### GENERAL ADA GUIDELINES:

- 65. HAND RAILING NOTES:
- HANDRAILS ARE REQUIRED ON RAMPS THAT RISE MORE THAN 6 INCHES OR ARE LONGER THAN 72 INCHES. HANDRAILS MUST BE BETWEEN 34 INCHES

  AND 38 INCHES AROUS THE WALKING SUBFACE AND BE FASY TO ORID.
- AND 38 INCHES ABOVE THE WALKING SURFACE AND BE EASY TO GRIP.

   HANDRAILS REQUIRED ON ALL STAIRS THAT EXCEED 3 RISERS.
- SEE DETAIL 5 ON SHEET L8.2 FOR HANDRAIL

### EROSION CONTROL MEASURES:

- 67. THOROUGHLY REVIEW THE SEDIMENT AND EROSION CONTROL PLAN.68. CONTRACTOR TO FINE GRADE AND ADD EROSION CONTROL MATTING AND NATURAL SITE DEBRIS AT ACCESS AREAS USED BY GEOTECHNICAL ENGINEERS
- FOR BORING SITES.

  69. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN FOURTEEN (14) DAYS AFTER WORK HAS CEASED, EXCEPT AS STATED BELOW.
- 70. WHERE STABILIZATION BY THE 14TH DAY IS PRECLUDED BY SNOW COVER OR FROZEN GROUND CONDITIONS STABILIZATION MEASURES MUST BE INITIATED AS SOON AS PRACTICABLE.
- 71. WHERE CONSTRUCTION ACTIVITY ON A PORTION OF THE SITE IS TEMPORARILY CEASED, AND EARTH—DISTURBING ACTIVITIES WILL BE RESUMED WITHIN 14 DAYS, TEMPORARY STABILIZATION MEASURES DO NOT HAVE TO BE INITIATED ON THAT PORTION OF THE SITE.
- 72. ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED ONCE EVERY CALENDAR WEEK. IF PERIODIC INSPECTION OR OTHER INFORMATION INDICATES THAT A BMP HAS BEEN INAPPROPRIATELY OR INCORRECTLY INSTALLED, THE PERMITTEE MUST ADDRESS THE NECESSARY REPLACEMENT OR MODIFICATION REQUIRED TO CORRECT THE BMP WITHIN 48 HOURS OF IDENTIFICATION. IF THIS OCCURS, NOTIFY LANDSCAPE ARCHITECT.
- 73. PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES, AS MAY BE REQUIRED, TO CONTROL SOIL EROSION DURING UTILITY CONSTRUCTION. ALL DISTURBED AREAS SHALL BE CLEANED, GRADED, AND STABILIZED WITH GRASSING IMMEDIATELY AFTER THE UTILITY INSTALLATION. FILL, COVER, AND TEMPORARY SEEDING AT THE END OF EACH DAY ARE RECOMMENDED. IF WATER IS ENCOUNTERED WHILE TRENCHING, THE WATER SHOULD BE FILTERED TO REMOVE ANY SEDIMENTS BEFORE BEING PUMPED BACK INTO ANY WATERS OF THE STATE.
- 74. ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION UNTIL THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION IN ORDER TO CONTROL EROSION AND/OR OFFSITE SEDIMENTATION. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE AND THE SITE IS STABILIZED.
- 75. THE CONTRACTOR MUST TAKE NECESSARY ACTION TO MINIMIZE THE TRACKING OF MUD ONTO PAVED ROADWAY(S) FROM CONSTRUCTION AREAS AND THE GENERATION OF DUST. THE CONTRACTOR SHALL DAILY REMOVE MUD/SOIL FROM PAVEMENT, AS MAY BE REQUIRED.

  76. TEMPORARY DIVERSION BERMS AND/OR DITCHES WILL BE PROVIDED AS

NEEDED DURING CONSTRUCTION TO PROTECT WORK AREAS FROM UPSLOPE

RUNOFF AND/OR TO DIVERT SEDIMENT-LADEN WATER TO APPROPRIATE TRAPS

- OR STABLE OUTLETS. THESE TEMPORARY BERMS AND DITCHES SHALL BE PROTECTED WITH A ROLLED EROSION AND SEDIMENT CONTROL PRODUCT UNTIL VEGETATION CAN BE ESTABLISHED.
- 77. ALL WATERS OF THE STATE (WOS), INCLUDING WETLANDS, ARE TO BE FLAGGED OR OTHERWISE CLEARLY MARKED IN THE FIELD. A DOUBLE ROW OF SILT FENCE IS TO BE INSTALLED IN ALL AREAS WHERE A 50-FOOT BUFFER CAN'T BE MAINTAINED BETWEEN THE DISTURBED AREA AND ALL WOS. A 10-FOOT BUFFER SHOULD BE MAINTAINED BETWEEN THE LAST ROW OF SILT FENCE AND ALL WOS.
- 78. LITTER, CONSTRUCTION DEBRIS, OILS, FUELS, AND BUILDING PRODUCTS WITH SIGNIFICANT POTENTIAL FOR IMPACT (SUCH AS STOCKPILES OF FRESHLY TREATED LUMBER) AND CONSTRUCTION CHEMICALS THAT COULD BE EXPOSED TO STORM WATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE IN STORM WATER DISCHARGES.
- 79. A COPY OF THE INSPECTION RECORDS, AND RAINFALL DATA MUST BE RETAINED AT THE CONSTRUCTION SITE OR A NEARBY LOCATION EASILY ACCESSIBLE DURING NORMAL BUSINESS HOURS, FROM THE DATE OF COMMENCEMENT OF CONSTRUCTION ACTIVITIES TO THE DATE THAT FINAL STABILIZATION IS REACHED.
- 80. INITIATE STABILIZATION MEASURES ON ANY EXPOSED STEEP SLOPE (3H:1V OR GREATER) WHERE LAND—DISTURBING ACTIVITIES HAVE PERMANENTLY OR TEMPORARILY CEASED, AND WILL NOT RESUME FOR A PERIOD OF 7 CALENDAR
- 81. MINIMIZE SOIL COMPACTION AND, UNLESS UNFEASIBLE, PRESERVE TOPSOIL.
- 82. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM EQUIPMENT AND VEHICLE WASHING, WHEEL WASH WATER, AND OTHER WASH WATERS. WASH WATERS MUST BE TREATED IN A SEDIMENT BASIN OR ALTERNATIVE CONTROL THAT
- PROVIDES EQUIVALENT OR BETTER TREATMENT PRIOR TO DISCHARGE.

  83. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM DEWATERING OF TRENCHES AND EXCAVATED AREAS. THESE DISCHARGES ARE TO BE ROUTED THROUGH
- APPROPRIATE BMP'S (SEDIMENT BASIN, FILTER BAG, ETC).

  84. MAINTAIN ALL BUFFER REQUIREMENTS AS INDICATED ON THE PLAN.
- 85. THE FOLLOWING DISCHARGES FROM SITES ARE PROHIBITED:
- 85.1. WASTEWATER FROM WASHOUT OF CONCRETE, UNLESS MANAGED BY AN APPROPRIATE CONTROL;
- RELEASE OILS, CURING COMPOUNDS, AND OTHER CONSTRUCTION MATERIALS;

85.2. WASTEWATER FROM WASHOUT AND CLEANOUT OF STUCCO, PAINT, FORM


85.3. FUELS, OILS, OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT

- OPERATION AND MAINTENANCE; AND
- 85.4. SOAPS OR SOLVENTS USED IN VEHICLE AND EQUIPMENT WASHING.
  86. AFTER CONSTRUCTION ACTIVITIES BEGIN, INSPECTIONS ARE EXPECTED TO BE CONDUCTED AT A MINIMUM OF AT LEAST ONCE EVERY CALENDAR WEEK AND MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE.









A WHITTIER PARK

Copyright © 2021, Equinox Environmento Consultation & Design, Inc.

BID SET

DATE
August 21, 2024

DRAWING SCALE

AS SHOWN

NOTE: If this drawing is not 24x36" it has been revised from its original size and the


scales noted on drawings/details are no


INDEX &


NOTES


NG NAME

















Field crews located the stream North of Beck Branch Road, the dilapidated house, old foundations, rock wall along the drive and the treeline on the property below the power line easement.

I, Marshall Wight, certify that this project was completed under my direct and responsible charge from an actual survey made under my supervision; that this bathymetric sonar survey was performed at the <u>95</u> percent confidence level to meet Federal Geographic Data Committee Standards; that this survey was performed to meet the requirements for a topographic/planimetric survey to the accuracy of Class A and vertical accuracy when applicable to the Class C standard, and that the original data was obtained on 11/18/22 that the survey was completed on 11/18/22; and all coordinates are based on NAD 83(2011) adjusted to site control and all elevations are based on NAVD 88.


12/8/2022 Marshall Wight
62C73F441B864C1...


Marshall Wight, PLS L-5034

Whittier Survey

Survey Report
Existing Condition Survey
Project # 08221054.00







BID SET


August 21, 2024


AS SHOWN

NOTE: If this drawing is not 24x36" it has been revised from its original size and the scales noted on drawings/details are no longer applicable.

WITHERSRAVENEL

SURVEY





### LEGEND

PROPERTY LINE

EXISTING CONTOURS (1FT)

EDGE OF EXISTING VEGETATION (APPROX)

EXISTING FENCE TO REMAIN

EXISTING UTILITY TO REMAIN

MAJOR CONTOUR (PROPOSED)

MINOR CONTOUR (PROPOSED)





DES	SIGN	BY:	DR	AWN	BY:	CHE	CKED	BY
DATE								
S								
REVISIONS								

County	(   	(
		L A K
Farms Rd.		
NC 28789		

Copyright © 2021, Equinox Environmental Consultation & Design, Inc.

HASE

BID SET

August 21, 2024

DRAWING SCALE


AS SHOWN

AS SHOWN

NOTE: If this drawing is not 24x36" it has been revised from its original size and the scales noted on drawings/details are no longer applicable.

DRAWING NAME

SITE PLAN




- UTILITY REMOVAL TO BE COORDINATED BETWEEN CONTRACTOR AND UTILITY PROVIDER. ENGINEERING SHEETS TO CONTAIN MORE DETAIL IN
- SEE GRADING PLANS FOR GRADING INFORMATION.
- TREE PROTECTION TO BE ESTABLISHED FOR ALL TREES ADJACENT TO GRADING EXTENTS.
- NOT ALL TREES ON SITE HAVE BEEN SURVEYED. UNLESS BEING GRADED THROUGH OR MARKED FOR REMOVAL, ALL TREES ARE TO BE PROTECTED AND MAINTAINED. ALL TREES TO BE DEMOLISHED ARE INDICATED WITH
- BRAMBLES AND OTHER NON-NATIVE INVASIVES TO BE REMOVED FROM PROJECT AREA WITHIN GRADING OR PLANTING EXTENTS. LOCATIONS OF THESE PLANTS TO BE IDENTIFIED IN THE FIELD.


### LEGEND

---- PROPERTY LINE EXISTING CONTOURS (1FT) EDGE OF EXISTING VEGETATION (APPROX) 


—— 3HO—— — EXISTING UTILITY TO REMAIN — SITE FEATURE TO BE DEMOLISHED



SITE PREPARATION







DES	ы:	DK	 οι.	CHE	Б1;
DATE					
6					
REVISIONS					

son County

JALLA WHITTIER PARK

et Farms Rd.
ier, NC 28789

Copyright © 2021, Equinox Environmental Consultation & Design, Inc.

HASE

BID SET

August 21, 2024


AS SHOWN


NOTE: If this drawing is not 24x36" it has been revised from its original size and the scales noted on drawings/details are no longer applicable.


DRAWING NAME


LAYOUT PLAN


L 3, 0





















DE	SIGN	BY:	DR	AWN	BY:	CHE	CKED	ВҮ	
DATE									
S									
REVISIONS									

Jackson County  $\bigcirc \bigcup \bigcirc \bigcup \bigcirc \bigcup \bigcirc \bigcup$  Sunset Farms Rd. Whittier, NC 28789

Copyright © 2021, Equinox Environmental Consultation & Design, Inc.

BID SET

August 21, 2024

DRAWING SCALE


AS SHOWN


AS SHOWN


NOTE: If this drawing is not 24x36" it has been revised from its original size and the scales noted on drawings/details are no longer applicable.


MATERIALS
PLAN
ENLARGEMENT


\_4.1





















Jackson County		
QUALLA	X I I I I I I I I I I I I I I I I I I I	
Sunset Farms Rd.		
Whittier, NC 28789		

Copyright © 2021, Equinox Environmental Consultation & Design, Inc.

August 21, 2024

GRADING & DRAINAGE ENLARGEMENT





LEGEI	ND
	EXISTING TOPO
	PROPOSED TOPO
	WETTED PERIMETER
	PIPE
	UNDERDRAIN
750	ENERGY DISSIPATOR
_	SWALE
	PERMANENT SWALE CHECK

CONVEYANCE ID	TYPE	LENGTH (FT.)	INVERT IN	INVERT OUT	SLOPE	BOTTOM WIDTH (Ft.)	DITCH DEPTH (In.)	CHANNE L LINING	CHECK TREATMENT
Α	SWALE	122	1930	1914	13.1%	1	12	SC150BN	YES
В	SWALE	41	1934	1927	17.1%	0.5	12	SC150BN	YES
С	SWALE	167	1952	1932	6%-20%	1.5	12	SC150BN	YES
D	SWALE	56	1944	1938	10.7%	1	12	S75BN	
E	SWALE	66	1950	1945	7.6%	2	12	S75BN	
F	SWALE	184	1971	1952	10.3%	1.5	12	SC150BN	YES
G	SWALE	157	1967	1952	9.6%	1.5	12	SC150BN	YES
Н	SWALE	211	1964	1947	8.1%	1	6	S75BN	
1	SWALE	87	1967.5	1964.5	3.4%	1	6	NA	
J	SWALE	89	1975	1967	9.0%	2	6	S75BN	
K	SWALE	102	1964.75	1962.75	2.0%	2	6	NA	
NOTE: SIDE SLC	PES NO ST	EEPER THA	NN 3:1						
REFER TO PLAN	TING PLAN	FOR SURF	ACE TREA	TMENT					

811.	
ow what's <b>below.</b> <b>Call</b> before you dig.	

STRUCTURE ID	TYPE	TOP TREATMENT	RIM ELEV.	DETAIL	NOTES
DI 1	CONCRETE BOX	OPEN THROAT, FOUR SIDES	1931.90	3/L8.5	
DI 2	CONCRETE BOX	OPEN THROAT, FOUR SIDES	1925.90	3/L8.5	
DI 3	CONCRETE BOX	OPEN THROAT, FOUR SIDES	1943.20	3/L8.5	ANTI-SEEP COLLAR
DI 4	CONCRETE BOX	OPEN THROAT, FOUR SIDES	1952.00	3/L8.5	
DI 5	CONCRETE BOX	OPEN THROAT, FOUR SIDES	1952.30	3/L8.5	
DI 6	CONCRETE BOX	OPEN THROAT, FOUR SIDES	1981.00	3/L8.5	ANTI-SEEP COLLAR
DI 7	CONCRETE BOX	OPEN THROAT, FOUR SIDES	1984.20	3/L8.5	
DI 8	CONCRETE BOX	OPEN THROAT, FOUR SIDES	1965.80	3/L8.5	
DI 9	CONCRETE BOX	OPEN THROAT, FOUR SIDES	1962.80	3/L8.5	
AD 1	AREA CATCHMENT	METAL GRATE	1981.90	NA	
AD 2	AREA CATCHMENT	METAL GRATE	1983.20	NA	
W 1	CONCRETE WEIR	WEIR NOTCH	1971.50	6/L8.5	
LS 1	LEVEL SPREADER	SMOOTH CONCRETE	1942.00	7/L8.5	LENGTH TO BE 15
LS 2	LEVEL SPREADER	SMOOTH CONCRETE	1977.00	7/L8.5	LENGTH TO BE 25
LS 3	LEVEL SPREADER	SMOOTH CONCRETE	1956.20	7/L8.5	LENGTH TO BE 15

### DESCRIPTION OF THE STORMWATER SYSTEMS

- BIORETENTION
- 1. THIS PROJECT UTILIZES TWO BIORETENTION CELLS.
- BIORETENTION IS DESIGNED TO FILTER WATER THROUGH BIORETENTION MEDIA BEFORE EXITING THE SYSTEM THROUGH UNDERDRAINS.
- 3. THE MOST COMMON FAILURE POINTS OF BIORETENTION IS WATER BYPASSING FILTRATION BY RUNNING DOWN ALONG THE DROP INLET AND FOLLOWING THE OUTFALL PIPE (ON THE OUTSIDE). THIS IS AVOIDED THROUGH THE USE OF AN ANTI-SEEP COLLAR AND PROPER COMPACTION AROUND THE PIPE, DROP INLET AND THE EMBANKMENT OF THE BIORETENTION CELL.

### LEVEL SPREADER:

- 1. THIS PROJECT UTILIZES THREE LEVEL SPREADERS.
- 2. LEVEL SPREADERS ARE DESIGNED TO SPREAD WATER EVENLY ACROSS THE CONCRETE SPREADER. THE LEVEL SPREADER IS COMPOSED OF THREE PARTS, THE BLIND SWALE, THE LEVEL SPREADER, AND THE TRANSITION ZONE OR VERGE.
- THE BLIND SWALE MOVES WATER BEHIND THE LEVEL SPREADER AND ALLOWS WATER TO ACCUMULATE BEHIND THE LEVEL SPREADER SUCH THAT THE WATER WILL TOP THE LEVEL SPREADER FOR THE FULL LENGTH AT ONE TIME.
- TO ENSURE EVEN SPREAD, THE CONCRETE LEVEL SPREADER SHOULD BE AT THE SAME ELEVATION ALL THE WAY ACROSS. A LOW POINT OR EDGE WILL CAUSE THE WATER TO FUNNEL AND CAN CAUSE SCOUR DOWN HILL.
- THE VERGE DISSIPATES THE ENERGY OFF OF THE SPREADER AND ALLOWS FOR SOME INFILTRATION.
- 3. THE MOST COMMON FAILURES OF A LEVEL SPREADER ARE SCOUR AROUND THE EDGES OF THE SPREADER AND THE SETTLING OF THE SPREADER CAUSING WATER TO CHANNELIZE. TO AVOID THIS, THE LEVEL SPREADER SHOULD BE EMBEDDED ON EITHER SIDE INTO COMPACTED EARTH AND SET DEEP ENOUGH ON TOP OF COMPACTED EARTH. BE SURE TO COMPACT SUB-BASE TO 98% PROCTOR PRIOR TO PLACING IN THE AGGREGATE BASE COARSE. COMPACT AGGREGATE BASE COARSE (CABC) TO 98% PROCTOR PRIOR TO SETTING CONCRETE FORMS. IF BEDROCK IS HIT WHEN DIGGING FOR FOOTERS, TIE FOOTERS DIRECTLY TO BEDROCK.

### **GENERAL NOTES**

- 1. SEDIMENTATION OF THE STORMWATER CONTROL MEASURES WILL CAUSE FAILURE, THEREFORE, INSTALL ALL STORMWATER CONTROL MEASURES ONLY AFTER ALL
- SEDIMENT AND EROSION ON-SITE IS CONTROLLED AND SITE IS STABILIZED AND SEEDED.
- 2. ALL SIDE SLOPES SHALL BE 3:1 OR SHALLOWER.
- 3. FOR SWALES RECEIVING CHECK TREATMENT, REFER TO 8/L8.3


					T
PIPE ID	TYPE	INV IN	INV OUT	LENGTH (FT)	SIZE (In.)
PIPE 1	HDPE (smooth)	1911.50	1911.00	43	24
PIPE 2	HDPE (smooth)	1925.00	1922.00	38	15
PIPE 3	HDPE (smooth)	1919.00	1911.00	38	15
PIPE 4	HDPE (smooth)	1940.50	1940.00	27	18
PIPE 5	HDPE (smooth)	1950.50	1950.20	28	15
PIPE 6	HDPE (smooth)	1950.10	1949.60	55	15
PIPE 7	HDPE (smooth)	1946.00	1943.50	28	15
PIPE 8	HDPE (smooth)	1981.25	1981.00	21	6
PIPE 9	HDPE (smooth)	1982.00	1981.50	19	6
PIPE 10	HDPE (smooth)	1977.85	1977.10	74	15
PIPE 11	HDPE (smooth)	1979.00	1978.00	35	15
PIPE 12	HDPE (smooth)	1961.00	1960.00	49	15
PIPE 13	HDPE (smooth)	1958.20	1957.20	26	15
		•			




TREATMET OUTFALL

DEPTH (In.) | ELEVATION | VOLUME (CF) | SLOPES | DETAILS







Copyright © 2021, Equinox Environmental Consultation & Design, Inc.

BID SET

August 21, 2024

AS SHOWN been revised from its original size and the scales noted on drawings/details are no longer applicable.

STORMWATER

CONVEYANCE ID	TYPE	LENGTH (FT.)	INVERT IN	INVERT OUT	SLOPE	BOTTOM WIDTH (Ft.)	DITCH DEPTH (In.)	CHANNE L LINING	CHECK TREATMENT
А	SWALE	122	1930	1914	13.1%	1	12	SC150BN	YES
В	SWALE	41	1934	1927	17.1%	0.5	12	SC150BN	YES
С	SWALE	167	1952	1932	6%-20%	1.5	12	SC150BN	YES
D	SWALE	56	1944	1938	10.7%	1	12	S75BN	
E	SWALE	66	1950	1945	7.6%	2	12	S75BN	
F	SWALE	184	1971	1952	10.3%	1.5	12	SC150BN	YES
G	SWALE	157	1967	1952	9.6%	1.5	12	SC150BN	YES
Н	SWALE	211	1964	1947	8.1%	1	6	S75BN	
I	SWALE	87	1967.5	1964.5	3.4%	1	6	NA	
J	SWALE	89	1975	1967	9.0%	2	6	S75BN	
К	SWALE	102	1964.75	1962.75	2.0%	2	6	NA	

REFER TO PLANTING PLAN FOR SURFACE TREATMENT. REFER TO 8/L8.5 FOR CHECK DETAIL.

STRUCTURE ID	TYPE	TOP TREATMENT	RIM ELEV.	DETAIL	NOTES
DI 1	CONCRETE BOX	OPEN THROAT, FOUR SIDES	1931.90	3/L8.5	
DI 2	CONCRETE BOX	OPEN THROAT, FOUR SIDES	1925.90	3/L8.5	
DI 3	CONCRETE BOX	OPEN THROAT, FOUR SIDES	1943.20	3/L8.5	ANTI-SEEP COLLAR
DI 4	CONCRETE BOX	OPEN THROAT, FOUR SIDES	1952.00	3/L8.5	
DI 5	CONCRETE BOX	OPEN THROAT, FOUR SIDES	1952.30	3/L8.5	
DI 6	CONCRETE BOX	OPEN THROAT, FOUR SIDES	1981.00	3/L8.5	ANTI-SEEP COLLAR
DI 7	CONCRETE BOX	OPEN THROAT, FOUR SIDES	1984.20	3/L8.5	
DI 8	CONCRETE BOX	OPEN THROAT, FOUR SIDES	1965.80	3/L8.5	
DI 9	CONCRETE BOX	OPEN THROAT, FOUR SIDES	1962.80	3/L8.5	
AD 1	AREA CATCHMENT	METAL GRATE	1981.90	NA	
AD 2	AREA CATCHMENT	METAL GRATE	1983.20	NA	
W 1	CONCRETE WEIR	WEIR NOTCH	1971.50	6/L8.5	
LS 1	LEVEL SPREADER	SMOOTH CONCRETE	1942.00	7/L8.5	LENGTH TO BE 15'
LS 2	LEVEL SPREADER	SMOOTH CONCRETE	1977.00	7/L8.5	LENGTH TO BE 25'
LS 3	LEVEL SPREADER	SMOOTH CONCRETE	1956.20	7/L8.5	LENGTH TO BE 15'

PIPE ID	TYPE	INV IN	INV OUT	LENGTH (FT)	SIZE (In.)
PIPE 1	HDPE (smooth)	1911.50	1911.00	43	24
PIPE 2	HDPE (smooth)	1925.00	1922.00	38	15
PIPE 3	HDPE (smooth)	1919.00	1911.00	38	15
PIPE 4	HDPE (smooth)	1940.50	1940.00	27	18
PIPE 5	HDPE (smooth)	1950.50	1950.20	28	15
PIPE 6	HDPE (smooth)	1950.10	1949.60	55	15
PIPE 7	HDPE (smooth)	1946.00	1943.50	28	15
PIPE 8	HDPE (smooth)	1981.25	1981.00	21	6
PIPE 9	HDPE (smooth)	1982.00	1981.50	19	6
PIPE 10	HDPE (smooth)	1977.85	1977.10	74	15
PIPE 11	HDPE (smooth)	1979.00	1978.00	35	15
PIPE 12	HDPE (smooth)	1961.00	1960.00	49	15
PIPE 13	HDPE (smooth)	1958.20	1957.20	26	15

SCM ID	ТҮРЕ	TREATMET DEPTH (In.)	OUTFALL ELEVATION	STORAGE VOLUME (CF)	MAX SIDE SLOPES	DETAILS
SCM 1	BIORETENTION	12	1943.25	1,818	3:1	4/L8.3
SCM 2	BIORETENTION	12	1981.50	795	3:1	4/L8.3

### LEGEND

EXISTING TOPO

PROPOSED TOPO
WETTED PERIMETER

--- PI


--- UNDERDRAIN


ENERGY DISSIPATOR


- SWA

PERMANENT SWALE CHECK













DES	SIGN	BY:	DR	AWN	BY:	CHE	CKED	BY:
DATE								
"								
REVISIONS								

Jackson County  $\bigcirc \bigcup A \sqsubseteq \sqsubseteq A$   $\bigcirc \bigvee \coprod \bigcap \sqsubseteq \sqsubseteq$  Sunset Farms Rd. Whittier, NC 28789

Copyright © 2021, Equinox Environmental Consultation & Design, Inc.

ASE

BID SET

August 21, 2024

AWING SCALE

AS SHOWN

NOTE: If this drawing is not 24x36" it been revised from its original size and


been revised from its original size and the scales noted on drawings/details are no longer applicable.


RAWING NAME

STORMWATER

PLAN

ENLARGEMENT






PIPE ID	ТҮРЕ	INV IN	INV OUT	LENGTH (FT)	SIZE (In.)
PIPE 1	HDPE (smooth)	1911.50	1911.00	43	24
PIPE 2	HDPE (smooth)	1925.00	1922.00	38	15
PIPE 3	HDPE (smooth)	1919.00	1911.00	38	15
PIPE 4	HDPE (smooth)	1940.50	1940.00	27	18
PIPE 5	HDPE (smooth)	1950.50	1950.20	28	15
PIPE 6	HDPE (smooth)	1950.10	1949.60	55	15
PIPE 7	HDPE (smooth)	1946.00	1943.50	28	15
PIPE 8	HDPE (smooth)	1981.25	1981.00	21	6
PIPE 9	HDPE (smooth)	1982.00	1981.50	19	6
PIPE 10	HDPE (smooth)	1977.85	1977.10	74	15
PIPE 11	HDPE (smooth)	1979.00	1978.00	35	15
PIPE 12	HDPE (smooth)	1961.00	1960.00	49	15
PIPE 13	HDPE (smooth)	1958.20	1957.20	26	15

CONVEYANCE ID	TYPE	LENGTH (FT.)	INVERT IN	INVERT OUT	SLOPE	BOTTOM WIDTH (Ft.)	DITCH DEPTH (In.)	CHANNE L LINING	CHECK TREATMENT
А	SWALE	122	1930	1914	13.1%	1	12	SC150BN	YES
В	SWALE	41	1934	1927	17.1%	0.5	12	SC150BN	YES
С	SWALE	167	1952	1932	6%-20%	1.5	12	SC150BN	YES
D	SWALE	56	1944	1938	10.7%	1	12	S75BN	
E	SWALE	66	1950	1945	7.6%	2	12	S75BN	
F	SWALE	184	1971	1952	10.3%	1.5	12	SC150BN	YES
G	SWALE	157	1967	1952	9.6%	1.5	12	SC150BN	YES
Н	SWALE	211	1964	1947	8.1%	1	6	S75BN	
ı	SWALE	87	1967.5	1964.5	3.4%	1	6	NA	
J	SWALE	89	1975	1967	9.0%	2	6	S75BN	
К	SWALE	102	1964.75	1962.75	2.0%	2	6	NA	
						•	•	•	

11072. 3122 3237 23 713 37227 211 777 11 3.1
REFER TO PLANTING PLAN FOR SURFACE TREATMENT

STRUCTURE ID	TYPE	TOP TREATMENT	RIM ELEV.	DETAIL	NOTES
DI 1	CONCRETE BOX	OPEN THROAT, FOUR SIDES	1931.90	3/L8.5	
DI 2	CONCRETE BOX	OPEN THROAT, FOUR SIDES	1925.90	3/L8.5	
DI 3	CONCRETE BOX	OPEN THROAT, FOUR SIDES	1943.20	3/L8.5	ANTI-SEEP COLLAR
DI 4	CONCRETE BOX	OPEN THROAT, FOUR SIDES	1952.00	3/L8.5	
DI 5	CONCRETE BOX	OPEN THROAT, FOUR SIDES	1952.30	3/L8.5	
DI 6	CONCRETE BOX	OPEN THROAT, FOUR SIDES	1981.00	3/L8.5	ANTI-SEEP COLLAR
DI 7	CONCRETE BOX	OPEN THROAT, FOUR SIDES	1984.20	3/L8.5	
DI 8	CONCRETE BOX	OPEN THROAT, FOUR SIDES	1965.80	3/L8.5	
DI 9	CONCRETE BOX	OPEN THROAT, FOUR SIDES	1962.80	3/L8.5	
AD 1	AREA CATCHMENT	METAL GRATE	1981.90	NA	
AD 2	AREA CATCHMENT	METAL GRATE	1983.20	NA	
W 1	CONCRETE WEIR	WEIR NOTCH	1971.50	6/L8.5	
LS 1	LEVEL SPREADER	SMOOTH CONCRETE	1942.00	7/L8.5	LENGTH TO BE 15
LS 2	LEVEL SPREADER	SMOOTH CONCRETE	1977.00	7/L8.5	LENGTH TO BE 25
LS 3	LEVEL SPREADER	SMOOTH CONCRETE	1956.20	7/L8.5	LENGTH TO BE 15

SCN	M ID			OUTFALL ELEVATION	STORAGE VOLUME (CF)	MAX SIDE SLOPES	DETAILS
SCN	M 1	BIORETENTION	12	1943.25	1,818	3:1	4/L8.3
SCI	M 2	BIORETENTION	12	1981.50	795	3:1	4/L8.3





	DESIGN BY:		DR	DRAWN BY:			CHECKED BY		
ļ	DATE								
	REVISIONS								
	-								

	WHITIER			
n County	$\forall$	Farms Rd.	., NC 28789	


Copyright © 2021, Equinox Environmental Consultation & Design, Inc.


BID SET


August 21, 2024


AS SHOWN NOTE: If this drawing is not 24x36" it has been revised from its original size and the scales noted on drawings/details are no longer applicable.


STORMWATER PLAN ENLARGEMENT





















PLANT S	CHED	ULE			
SYMBOL	CODE	QTY	BOTANICAL / COMMON NAME	HEIGHT	CONTAINER
TREES					
	AMAR	9	Amelanchier arborea Downy Serviceberry	6` Ht.	B&B
£	CHVI	8	Chionanthus virginicus White Fringetree	6` Ht.	B&B
Solvening September 1998	GLTR	3	Gleditsia triacanthos inermis 'Suncole' Sunburst® Honey Locust	10` Ht.	B&B
•	LITU	6	Liriodendron tulipifera Tulip Poplar	10` Ht.	B&B
•	NYSY	10	Nyssa sylvatica Tupelo	10` Ht.	B&B
	PLOC	11	Platanus occidentalis American Sycamore	10` Ht.	B&B
	QUFA	9	Quercus falcata Southern Red Oak	10` Ht.	B&B
SYMBOL	CODE	QTY	BOTANICAL / COMMON NAME	SIZE	CONTAINER
SHRUBS  ①	ARME	14	Aronia melanocarpa Black Chokeberry	3 gal.	Pot
$\odot$	CAAM	6	Callicarpa americana American Beautyberry	5 gal.	Pot
$\odot$	CAFL	15	Calycanthus floridus Sweetshrub	3 gal.	Pot
$\odot$	CEOS	12	Cephalanthus occidentalis 'SMCOSS' TM Sugar Shack Buttonbush	5 gal.	Pot
$\bigcirc$	DIKO	23	Diervilla x `G2X88544` TM Kodiak Orange Diervilla	3 gal.	Pot
(*)	FOBL	22	Fothergilla gardenii 'Blue Mist' Blue Mist Dwarf Fothergilla	3 gal.	Pot
	HYQU	4	Hydrangea quercifolia Oakleaf Hydrangea	5 gal.	Pot
<b>①</b>	HYDE	25	Hypericum densiflorum Bushy St. John's Wort	3 gal.	Pot
0	ILGL 19 Ilex glabra `Densa` 5 gal.  Ilex verticillata		5 gal.	Pot	
$\odot$	ILVE	12	Winterberry 1 male plant for a maximum of 6 female plants. If not straight species, males and females to be of corresponding cultivars.	10 gal.	Pot
$\odot$	ITVI	17	Itea virginica 'Sprich' Little Henry® Sweetspire	3 gal.	Pot
	LIBE	9	Lindera benzoin Spicebush	10 gal.	Pot
$\bigcirc$	PHOP	12	Physocarpus opulifolius 'Dart's Gold' Dart's Gold Ninebark	5 gal.	Pot
0	RHAR	49	Rhus aromatica 'Gro-Low' Gro-Low Fragrant Sumac	5 gal.	Pot

SYMBOL	CODE	QTY	BOTANICAL / COMMON NAME	SIZE	SPACING
GROUND (	COVERS				
		152 sf	SHADE MIX		
	HEBB	28	Heuchera x 'Blackberry Ice' Dolce® Blackberry Ice Coral Bells	#1	40% @ 18" o.c.
	PHDI	21	Phlox divaricata 'Blue Moon'	#1	30% @ 18" o.c.
	ZIAUM	21	Blue Moon Woodland Phlox Zizia aurea	#1	30% @ 18" o.c.
	2 10111	1,180 sf	Golden Alexander PERENNIAL MIX A	"	
	AOTU		Asclepias tuberosa	1 and	20% @ 24"
	ASTU	92	Butterfly Milkweed Rudbeckia fulgida	1 gal.	30% @ 24" o.c.
	RUFU	122	Coneflower Stokesia laevis	#1	40% @ 24" o.c.
	STLA	163	Stokes' Aster	#1	30% @ 18" o.c.
		2,183 sf	PERENNIAL MIX B		
	MOJA	141	Monarda didyma 'Jacob Cline' Jacob Cline Bee Balm	#1	25% @ 24" o.c.
	PYVI	114	Pycnanthemum virginianum Mountain Mint	#1	20% @ 24" o.c.
	SONI	355	Sorghastrum nutans 'Indian Steel' Indian Steel Indian Grass	plug	35% @ 18" o.c.
Z XX	VESU	74	Vernonia x 'Summer's Swan Song' Swan Song Ironweed	1 gal.	20% @ 30" o.c.
		1,343 sf	PERENNIAL MIX C		
	EUPU	122	Eutrochium purpureum `Baby Joe` Baby Joe Dwarf Joe Pye Weed	#1	35% @ 24" o.c.
	MURE	186	Muhlenbergia reverchonii Seep Muhly	plug	30% @ 18" o.c.
	SORU	54	Solidago rugosa 'Fireworks'	#1	35% @ 36" o.c.
	- 5.10	439 sf	Fireworks Wrinkleleaf Goldenrod PERENNIAL MIX D		
	41101		Andropogon glomeratus	D: 1	250/ @ 24"
	ANGL	40	Bushy Bluestem Helenium autumnale	Pint	35% @ 24" o.c.
	HEAU	23	Sneezeweed Vernonia noveboracensis	#1	20% @ 24" o.c.
	VENO	29	Comon Ironweed  Veronicastrum virginicum	#2	25% @ 24" o.c.
	VEVI	10	Culver's Root	1 gal.	20% @ 36" o.c.
		1,707 sf	PERENNIAL MIX E		
	ASIN	158	Asclepias incarnata Swamp Milkweed	#1	20% @ 18" o.c.
	CAST	315	Carex stricta Tussock Sedge	plug	40% @ 18" o.c
	HEAU	111	Helenium autumnale Sneezeweed	#1	25% @ 24" o.c.
	STLA	118	Stokesia laevis Stokes' Aster	#1	15% @ 18" o.c.
		457 sf	FERN MIX		
	DEPU	35	Dennstaedtia punctilobula Hay-scented Fern	#1	30% @ 24" o.c.
	OSCI	31	Osmunda cinnamomea	#1	40% @ 30" o.c.
	POAC	63	Cinnamon Fern Polystichum acrostichoides	#1	30% @ 18" o.c.
<u>//////</u>			Christmas Fern	// -	
GRASSES	& SEDGES BOGR	213	Bouteloua gracilis	plug	18" o.c.
			Blue Grama Carex stricta		
	CAST	43	Tussock Sedge Eragrostis spectabilis	plug	18" o.c.
	ERSP	399	Purple Lovegrass	plug	12" o.c.
	MURE	74	Muhlenbergia reverchonii Seep Muhly	plug	18" o.c.
	scsc	318	Schizachyrium scoparium 'Carousel'	#1	24" o.c.
	SPHE	76	Carousel Little Bluestem Sporobolus heterolepis	1 gal.	36" o.c.
<u> </u>	SPHE	76	Prairie Dropseed	ı yaı.	36 O.C.
PERENNIA	-		Amsonia hubrichtii	1.	
	AMHU	35	Arkansas Bluestar Amsonia tabernaemontana	1 gal.	36" o.c.
	AMTA	113	Eastern Bluestar	#1	18" o.c.
	COVE	10	Coreopsis verticillata 'Moonbeam' Moonbeam Tickseed	#1	24" o.c.
× × × × × × × × × × × × × × × × × × ×	GEMA	45	Geranium maculatum Spotted Geranium	#1	18" o.c.
	IRCR	57	Iris cristata Dwarf Crested Iris	#1	12" o.c.
w W W	PYVI	15	Pycnanthemum virginianum Mountain Mint	#1	24" o.c.
	ZIAUM	4	Zizia aurea Golden Alexander	#1	18" o.c.
	1		Golden Alexandel		
SOD/SEED			ERNMX-303		
+ + + + + + + + + + + + + + + + + + + +	NCMM	13,318 sf	NC Mountains UPL Meadow Mix Apply at rate of 20 lbs/acre. See	seed	
+ + + + + + + + + + + + + + + + + + +			Ernst Seeds for appropriate cover crop and rate of application.		
	TURF	119,041 sf	Turf Seed	seed	

\* NOTE: SOME GROUNDCOVERS AND GRASSES ARE CALLED OUT IN MIXES ON PLANTING SHEETS. THESE ARE <u>NOT</u> SEED MIXES; THEY ARE PLUGS OR POTS. MIXES ARE TO BE PLANTED IN GROUPS BY SPECIES, WITH SPECIES DISTRIBUTED THROUGHOUT THE PLANTING AREA. MINIMUM GROUPING TO BE 3, NO EVEN NUMBERS, AS IS POSSIBLE.




NOTES:

1. WATER THOROUGHLY IMMEDIATELY AFTER PLANTING AND WATER WEEKLY UNTIL ESTABLISHED.




### PERENNIAL PLANTING (TYPICAL SECTION)

SCALE: NOT TO SCALE




2 SHRUB PLANTING (TYPICAL SECTION)

SCALE: NOT TO SCALE









NOTES:


 TREES AND SHRUBS TO BE PLANTED AS SHOWN ON PLAN
 USE DIBBLE TO PLANT PLUGS.

■ PLUG SPACING











1. USE A SPADE AND CUT IN SOIL.

- 2. REMOVE SPADE AND INSERT SEEDLING SO THAT THE ROOT COLLAR IS JUST BELOW GROUND SURFACE WITH ROOTS FACING STRAIGHT DOWN IN THE PLANTING HOLE.
- 3. INSERT SPADE 3 INCHES TO ONE SIDE OF THE SEEDLING/PLUG AND PULL HANDLE TO CLOSE THE BOTTOM OF THE HOLE.
- 4. PUSH HANDLE OF SPADE FORWARD TO CLOSE THE TOP OF THE HOLE. OPEN PLANTING HOLE LARGE ENOUGH TO ACCOMMODATE ROOTS.
- 5. REMOVE SPADE AND CAREFULLY CLOSE THE OPENING BY TAMPING GENTLY WITH A TAMPER OR HEEL BEING CAREFUL NOT TO INJURE THE SEEDLING.









$\nearrow$	
⊆ _	Sunset Farms Kd. Whittier, NC 28789

Copyright © 2021, Equinox Environmental Consultation & Design, Inc.

BID SET

August 21, 2024

DRAWING SCALE


AS SHOWN

NOTE: If this drawing is not 24×36" it

NOTE: If this drawing is not 24x36" it has been revised from its original size and the scales noted on drawings/details are no longer applicable.

PLANT SCHEDULE & DETAILS

7 \_ \_



	LEGEND	
SYMBOL	DESCRIPTION	DETAIL
\/\\	LIMIT OF DISTURBANCE	
	EROSION CONTROL MATTING	4/ EC2.0
	OUTLET PROTECTION (ENERGY DISSIPATER)	6/ EC2.0
	INLET PROTECTION	1/ EC2.0
-0000	TREE SAVE ZONE	
	REINFORCED SILT FENCE	7/ EC2.0
—— TDD ——— TDD ———	TEMPORARY DIVERSION DITCH	5/ EC2.0
+ + + + + + + + + + + + + + + + + + + +	TEMPORARY SEED	4/ EC2.1
ST 💨	SEDIMENT TRAP/SPILLWAY	1/ EC 2.2
	PERMANENT PIPE	
	SEDIMENT SOCK	1/ EC2.1
0000	ROCK CHECK DAM	2/ EC2.1
(Alberta	SURFACE ROUGHENING	3/ EC2.1

EROSION CONTROL MEASURE NOTES:

THOROUGHLY REVIEW THE SEDIMENT AND EROSION CONTROL PLAN, ADDING EXTRA AS NECESSARY TO ELIMINATE SEDIMENTATION OFFSITE.


- 2. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN SEVEN (7) DAYS AFTER WORK HAS CEASED, EXCEPT AS STATED BELOW.
- 3. WHERE STABILIZATION BY THE 7TH DAY IS PRECLUDED BY SNOW COVER OR FROZEN GROUND CONDITIONS STABILIZATION MEASURES MUST BE INITIATED AS SOON AS
- 4. ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED ONCE EVERY CALENDAR WEEK. IF PERIODIC INSPECTION OR OTHER INFORMATION INDICATES THAT A BMP HAS BEEN INAPPROPRIATELY OR INCORRECTLY INSTALLED, THE PERMITTEE MUST ADDRESS THE NECESSARY REPLACEMENT OR MODIFICATION REQUIRED TO CORRECT THE BMP WITHIN 48 HOURS OF IDENTIFICATION. IF THIS OCCURS, NOTIFY LANDSCAPE ARCHITECT.
- 5. PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES, AS MAY BE REQUIRED, TO CONTROL SOIL EROSION DURING UTILITY CONSTRUCTION. ALL DISTURBED AREAS SHALL BE CLEANED, GRADED, AND STABILIZED WITH GRASSING IMMEDIATELY AFTER THE UTILITY INSTALLATION. FILL, COVER, AND TEMPORARY SEEDING AT THE END OF EACH DAY ARE RECOMMENDED. IF WATER IS ENCOUNTERED WHILE TRENCHING, THE WATER SHOULD BE FILTERED TO REMOVE ANY SEDIMENTS BEFORE BEING PUMPED BACK INTO ANY WATERS OF THE STATE.
- 6. ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION UNTIL THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION IN ORDER TO CONTROL EROSION AND/OR OFFSITE SEDIMENTATION. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE AND THE SITE IS STABILIZED.
- 7. THE CONTRACTOR MUST TAKE NECESSARY ACTION TO MINIMIZE THE TRACKING OF MUD ONTO PAVED ROADWAY(S) FROM CONSTRUCTION AREAS AND THE GENERATION OF DUST. THE CONTRACTOR SHALL DAILY REMOVE MUD/SOIL FROM PAVEMENT, AS MAY BE REQUIRED. OTHER MEASURES TO REDUCE TRACKING MAY INCLUDE WASHING DOWN TRACKS OF HEAVY FOUIPMENT.
- 8. TEMPORARY DIVERSION BERMS AND/OR DITCHES WILL BE PROVIDED AS NEEDED DURING CONSTRUCTION TO PROTECT WORK AREAS FROM UPSLOPE RUNOFF AND/OR TO DIVERT SEDIMENT—LADEN WATER TO APPROPRIATE TRAPS OR STABLE OUTLETS. THESE TEMPORARY BERMS AND DITCHES SHALL BE PROTECTED WITH A ROLLED EROSION AND SEDIMENT CONTROL PRODUCT UNTIL VEGETATION CAN BE ESTABLISHED.
- 9. LITTER, CONSTRUCTION DEBRIS, OILS, FUELS, AND BUILDING PRODUCTS WITH SIGNIFICANT POTENTIAL FOR IMPACT (SUCH AS STOCKPILES OF FRESHLY TREATED LUMBER) AND CONSTRUCTION CHEMICALS THAT COULD BE EXPOSED TO STORM WATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE IN STORM WATER DISCHARGES.
- 10. A COPY OF THE INSPECTION RECORDS, AND RAINFALL DATA MUST BE RETAINED AT THE CONSTRUCTION SITE OR A NEARBY LOCATION EASILY ACCESSIBLE DURING NORMAL BUSINESS HOURS, FROM THE DATE OF COMMENCEMENT OF CONSTRUCTION ACTIVITIES TO THE DATE THAT FINAL STABILIZATION IS REACHED.
- 11. INITIATE STABILIZATION MEASURES ON ANY EXPOSED STEEP SLOPE (3H:1V OR GREATER) WHERE LAND—DISTURBING ACTIVITIES HAVE PERMANENTLY OR TEMPORARILY CEASED, AND WILL NOT RESUME FOR A PERIOD OF 7 CALENDAR DAYS.
- WILL NOT RESUME FOR A PERIOD OF 7 CALENDAR DAYS.

  12. MINIMIZE SOIL COMPACTION AND, UNLESS UNFEASIBLE, PRESERVE TOPSOIL FOR FUTURE
- 13. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM EQUIPMENT AND VEHICLE WASHING, WHEEL WASH WATER, AND OTHER WASH WATERS. WASH WATERS MUST BE TREATED IN A SEDIMENT BASIN OR ALTERNATIVE CONTROL THAT PROVIDES EQUIVALENT OR BETTER TREATMENT PRIOR TO DISCHARGE.
- 14. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM DEWATERING OF TRENCHES AND EXCAVATED AREAS. THESE DISCHARGES ARE TO BE ROUTED THROUGH APPROPRIATE BMP'S (SEDIMENT BASIN, FILTER BAG, ETC).
- 15. MAINTAIN ALL BUFFER REQUIREMENTS AS INDICATED ON THE PLAN.
- 16. THE FOLLOWING DISCHARGES FROM SITES ARE PROHIBITED:

PLANTING.

- 16.1. WASTEWATER FROM WASHOUT OF CONCRETE, UNLESS MANAGED BY AN APPROPRIATE CONTROL;
- 16.2. WASTEWATER FROM WASHOUT AND CLEANOUT OF STUCCO, PAINT, FORM RELEASE OILS, CURING COMPOUNDS, AND OTHER CONSTRUCTION MATERIALS;
- 16.3. FUELS, OILS, OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT OPERATION AND MAINTENANCE; AND
- 16.4. SOAPS OR SOLVENTS USED IN VEHICLE AND EQUIPMENT WASHING.
- 17. AFTER CONSTRUCTION ACTIVITIES BEGIN, INSPECTIONS ARE EXPECTED TO BE CONDUCTED AT A MINIMUM OF AT LEAST ONCE EVERY CALENDAR WEEK AND MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE.
- 18. IF THE SAME PERSON CONDUCTS THE LAND-DISTURBING ACTIVITY AND ANY RELATED BORROW OR WASTE ACTIVITY, THE RELATED BORROW OR WASTE ACTIVITY SHALL CONSTITUTE PART OF THE LAND-DISTURBING ACTIVITY UNLESS THE BORROW OR WASTE ACTIVITY IS REGULATED UNDER THE MINING ACT OF 1971, OR IS A LANDFILL REGULATED BY THE DIVISION OF WASTE MANAGEMENT. IF THE LAND-DISTURBING ACTIVITY AND ANY RELATED BORROW OR WASTE ACTIVITY ARE NOT CONDUCTED BY THE SAME PERSON, THEY SHALL BE CONSIDERED SEPARATE LAND-DISTURBING ACTIVITIES AND MUST BE PERMITTED EITHER THROUGH THE SEDIMENTATION POLLUTION CONTROL ACT AS A ONE-USE BORROW SITE OR THROUGH THE MINING ACT

Know what's below.
Call before you dig.





CAROLLINA CAROLL

DESIGN BY:		DR	DRAWN BY:			CHECKED BY		
DATE								
REVISIONS								

Set Farms Rd.
tier, NC 28789

Copyright © 2021, Equinox Environmental Consultation & Design, Inc.

ASE

BID SET

August 21, 2024

DRAWING SCALE


AS SHOWN

NOTE: If this drawing is not 24x36" it has

NOTE: If this drawing is not 24x36" it has been revised from its original size and the scales noted on drawings/details are no longer applicable.

EROSION CONTROL PLAN P1








	LEGEND	
SYMBOL	DESCRIPTION	DETAIL
~	LIMIT OF DISTURBANCE	
	EROSION CONTROL MATTING	4/ EC2.0
	OUTLET PROTECTION (ENERGY DISSIPATER)	6/ EC2.0
0 0	INLET PROTECTION	1/ EC2.0
-0000	TREE SAVE ZONE	
	REINFORCED SILT FENCE	7/ EC2.0
—— TDD ——— TDD ———	TEMPORARY DIVERSION DITCH	5/ EC2.0
+ + + + + + + + + + + + + + + + + + + +	TEMPORARY SEED	4/ EC2.1
ST	SEDIMENT TRAP/SPILLWAY	1/ EC 2.2
	PERMANENT PIPE	
	SEDIMENT SOCK	1/ EC2.1
<del>2000</del>	ROCK CHECK DAM	2/ EC2.1
LARA PA	SURFACE ROUGHENING	3/ EC2.1

THOROUGHLY REVIEW THE SEDIMENT AND EROSION CONTROL PLAN, ADDING EXTRA AS NECESSARY TO ELIMINATE SEDIMENTATION OFFSITE.

- STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN SEVEN (7) DAYS AFTER WORK HAS CEASED, EXCEPT AS STATED BELOW.
- WHERE STABILIZATION BY THE 7TH DAY IS PRECLUDED BY SNOW COVER OR FROZEN GROUND CONDITIONS STABILIZATION MEASURES MUST BE INITIATED AS SOON AS
- . ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED ONCE EVERY CALENDAR WEEK. IF PERIODIC INSPECTION OR OTHER INFORMATION INDICATES THAT A BMP HAS BEEN INAPPROPRIATELY OR INCORRECTLY INSTALLED, THE PERMITTEE MUST ADDRESS THE NECESSARY REPLACEMENT OR MODIFICATION REQUIRED TO CORRECT THE BMP WITHIN 48 HOURS OF IDENTIFICATION. IF THIS OCCURS, NOTIFY LANDSCAPE ARCHITECT.
- PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES, AS MAY BE REQUIRED, TO CONTROL SOIL EROSION DURING UTILITY CONSTRUCTION. ALL DISTURBED AREAS SHALL BE CLEANED, GRADED, AND STABILIZED WITH GRASSING IMMEDIATELY AFTER THE UTILITY INSTALLATION. FILL, COVER, AND TEMPORARY SEEDING AT THE END OF EACH DAY ARE RECOMMENDED. IF WATER IS ENCOUNTERED WHILE TRENCHING, THE WATER SHOULD BE FILTERED TO REMOVE ANY SEDIMENTS BEFORE BEING PUMPED BACK INTO ANY WATERS OF THE STATE.
- ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION UNTIL THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION IN ORDER TO CONTROL EROSION AND/OR OFFSITE SEDIMENTATION. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE
- THE CONTRACTOR MUST TAKE NECESSARY ACTION TO MINIMIZE THE TRACKING OF MUD ONTO PAVED ROADWAY(S) FROM CONSTRUCTION AREAS AND THE GENERATION OF DUST. THE CONTRACTOR SHALL DAILY REMOVE MUD/SOIL FROM PAVEMENT, AS MAY BE REQUIRED. OTHER MEASURES TO REDUCE TRACKING MAY INCLUDE WASHING DOWN TRACKS OF HEAVY
- 8. TEMPORARY DIVERSION BERMS AND/OR DITCHES WILL BE PROVIDED AS NEEDED DURING CONSTRUCTION TO PROTECT WORK AREAS FROM UPSLOPE RUNOFF AND/OR TO DIVERT SEDIMENT-LADEN WATER TO APPROPRIATE TRAPS OR STABLE OUTLETS. THESE TEMPORARY BERMS AND DITCHES SHALL BE PROTECTED WITH A ROLLED EROSION AND SEDIMENT CONTROL PRODUCT UNTIL VEGETATION CAN BE ESTABLISHED.
- 9. LITTER, CONSTRUCTION DEBRIS, OILS, FUELS, AND BUILDING PRODUCTS WITH SIGNIFICANT POTENTIAL FOR IMPACT (SUCH AS STOCKPILES OF FRESHLY TREATED LUMBER) AND CONSTRUCTION CHEMICAL'S THAT COULD BE EXPOSED TO STORM WATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE IN STORM WATER DISCHARGES.
- 10. A COPY OF THE INSPECTION RECORDS, AND RAINFALL DATA MUST BE RETAINED AT THE CONSTRUCTION SITE OR A NEARBY LOCATION EASILY ACCESSIBLE DURING NORMAL BUSINESS HOURS, FROM THE DATE OF COMMENCEMENT OF CONSTRUCTION ACTIVITIES TO THE DATE THAT FINAL STABILIZATION IS REACHED.
- 11. INITIATE STABILIZATION MEASURES ON ANY EXPOSED STEEP SLOPE (3H:1V OR GREATER) WHERE LAND-DISTURBING ACTIVITIES HAVE PERMANENTLY OR TEMPORARILY CEASED, AND WILL NOT RESUME FOR A PERIOD OF 7 CALENDAR DAYS.
- 12. MINIMIZE SOIL COMPACTION AND, UNLESS UNFEASIBLE, PRESERVE TOPSOIL FOR FUTURE PLANTING.
- 13. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM EQUIPMENT AND VEHICLE WASHING, WHEEL WASH WATER, AND OTHER WASH WATERS. WASH WATERS MUST BE TREATED IN A SEDIMENT BASIN OR ALTERNATIVE CONTROL THAT PROVIDES EQUIVALENT OR BETTER TREATMENT PRIOR TO DISCHARGE.
- 14. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM DEWATERING OF TRENCHES AND EXCAVATED AREAS. THESE DISCHARGES ARE TO BE ROUTED THROUGH APPROPRIATE BMP'S (SEDIMENT BASIN, FILTER BAG, ETC).
- 15. MAINTAIN ALL BUFFER REQUIREMENTS AS INDICATED ON THE PLAN.
- 16. THE FOLLOWING DISCHARGES FROM SITES ARE PROHIBITED:
- 16.1. WASTEWATER FROM WASHOUT OF CONCRETE, UNLESS MANAGED BY AN APPROPRIATE
- 16.2. WASTEWATER FROM WASHOUT AND CLEANOUT OF STUCCO, PAINT, FORM RELEASE OILS, CURING COMPOUNDS, AND OTHER CONSTRUCTION MATERIALS;
- 16.3. FUELS, OILS, OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT OPERATION AND MAINTENANCE; AND
- 16.4. SOAPS OR SOLVENTS USED IN VEHICLE AND EQUIPMENT WASHING.
- 17. AFTER CONSTRUCTION ACTIVITIES BEGIN, INSPECTIONS ARE EXPECTED TO BE CONDUCTED AT A MINIMUM OF AT LEAST ONCE EVERY CALENDAR WEEK AND MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE.
- 18. IF THE SAME PERSON CONDUCTS THE LAND-DISTURBING ACTIVITY AND ANY RELATED BORROW OR WASTE ACTIVITY, THE RELATED BORROW OR WASTE ACTIVITY SHALL CONSTITUTE PART OF THE LAND-DISTURBING ACTIVITY UNLESS THE BORROW OR WASTE ACTIVITY IS REGULATED UNDER THE MINING ACT OF 1971, OR IS A LANDFILL REGULATED BY THE DIVISION OF WASTE MANAGEMENT. IF THE LAND-DISTURBING ACTIVITY AND ANY RELATED BORROW OR WASTE ACTIVITY ARE NOT CONDUCTED BY THE SAME PERSON, THEY SHALL BE CONSIDERED SEPARATE LAND-DISTURBING ACTIVITIES AND MUST BE PERMITTED EITHER THROUGH THE SEDIMENTATION POLLUTION CONTROL ACT AS A ONE-USE BORROW SITE OR THROUGH THE MINING ACT.







14 O'Henry Ave. Suite 206 Asheville, NC 28801

t 828.253.6856 f 828.253.8256


Copyright © 2021, Equinox Environmental Consultation & Design, Inc.

BID SET

August 21, 2024

AS SHOWN been revised from its original size and the scales noted on drawings/details are no

**EROSION** CONTROL PLAN P2



EQUINOX

14 O'Henry Ave.
Suite 206
Asheville, NC 28801
t 828.253.6856
f 828.253.8256

SIGN BY: DRAWN BY: CHECKED I

DESIGN BY: DRAWN BY: CHECKED B

ounty
LLA WHITTIER PARK
ms Rd.
c 28789

Copyright © 2021, Equinox Environmental Consultation & Design, Inc.


BID SET

August 21, 2024

AS SHOWN

NOTE: If this drawing is not 24x36" it has been revised from its original size and the scales noted on drawings/details are no

EROSION CONTROL DETAILS



INSTALLATION:


1. INSTALL SEDIMENT TUBES BY LAYING THEM FLAT ON THE GROUND. CONSTRUCT A SMALL TRENCH TO A DEPTH THAT IS 20% OF THE SEDIMENT TUBE DIAMETER. LAY THE SEDIMENT TUBE IN THE TRENCH AND COMPACT THE UPSTREAM SEDIMENT TUBE SOIL INTERFACE. INSTALL ALL SEDIMENT TUBES SO NO GAPS EXIST BETWEEN THE SOIL TO PREVENT FLOW AND SEDIMENT FROM PASSING THROUGH THE FIELD JOINT. NEVER STACK SEDIMENT TUBES ON TOP OF ONE ANOTHER.

- SHOULD SEDIMENT TUBE BECOME DAMAGED DURING INSTALLATION, PLACE A STAKE ON BOTH SIDES OF THE DAMAGED AREA TERMINATING THE TUBE SEGMENT AND INSTALL NEW
- INSTALL SEDIMENT TUBES USING WOODEN STAKES (1" X 1") OR STEEL POSTS (STANDARD "U" OR "T" SECTIONS WITH A MINIMUM WEIGHT OF 1.25 POUNDS PER FOOT) A MINIMUM OF 4 FEET IN LENGTH PLACED ON 2' CENTERS. INTERTWINE THE STAKES WITH THE OUTER MESH ON THE DOWNSTREAM SIDE, AND DRIVE THE STAKES INTO THE GROUND TO A MINIMUM DEPTH OF 2' LEAVING LESS THAN 1' OF STAKE ABOVE THE EXPOSED

### INSPECTION AND MAINTENANCE: 1. INSPECT SEDIMENT TUBES AFTER INSTALLATION FOR GAPS UNDER THE SEDIMENT TUBES AND FOR GAPS BETWEEN THE JOINTS OF ADJACENT ENDS OF SEDIMENT TUBES. REPAIR

SEDIMENT SOCK


- RILLS, GULLIES, AND ALL UNDERCUTTING NEAR SEDIMENT TUBES. SEDIMENT TUBES SHALL ALSO BE INSPECTED AT LEAST ONCE EVERY CALENDAR WEEK. REMOVE ACCUMULATED SEDIMENT WHEN IT REACHES 1/3 THE HEIGHT OF THE SEDIMENT
- 3. LARGE DEBRIS, TRASH, AND LEAVES SHOULD BE REMOVED FROM IN FRONT OF THE SEDIMENT TUBE WHEN FOUND
- 4. REMOVE AND/OR REPLACE INSTALLED SEDIMENT TUBES AS REQUIRED TO ADAPT TO CHANGING CONSTRUCTION SITE CONDITIONS.
- 5. SEDIMENT TUBES SHALL REMAIN IN PLACE UNTIL THE DISTURBED AREAS ARPLAN SYMBOL
- . REMOVE ALL CONSTRUCTION MATERIAL AND SEDIMENT AND DISPOSE PROPERLY. BACKFILL ALL DEPRESSIONS AND GROUND DISTURBANCES CAUSED BY THE REMOVAL OF THE SEDIMENT TUBES.




STONE SHOULD BE PLACED OVER THE CHANNEL BANKS TO KEEP WATER FROM CUTTING AROUND THE DAM.

INSPECTION AND MAINTENANCE: REMOVE SEDIMENT ONCE IT HAS REACHED 1/3 THE HEIGHT OF THE CHECK DAM.

PLAN SYMBOL



FEW INCHES DEEP) APPEAR, RE-GRADE , RE-ROUGHEN AND RE-SEED IMPEDIATES YMBOL





1. TO SLOW EROSION, PERFORM SURFACE ROUGHENING (TRACKING) AS SOON AS POSSIBLE AFTER VEGETATION HAS BEEN REMOVED FROM SLOPE.

4. PERFORM TRACKING IMMEDIATELY AFTER GRADING ACTIVITIES HAVE CEASED (TEMPORARILY OR PERMANENTLY) IN AN AREA.

5. AVOID EXCESSIVE COMPACTING OF THE SOIL SURFACE WHEN TRACKING SINCE SOIL COMPACTION INHIBITS VEGETATION GROWTH AND CAUSES HIGHER RUNOFF RATES. AS FEW PASSES AS POSSIBLE SHOULD BE MADE WITH THE MACHINERY TO MINIMIZE COMPACTION.

INSPECTION AND MAINTENANCE:

1. ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED ONCE EVERY

2. IF RILLS (SMALL WATERCOURSES THAT HAVE STEEP SIDES AND USUALLY ARE ONLY A



ROCK CHECK DAM

SURFACE ROUGHENING

DAYS ON OTHER AREAS

PARTRIDGE PEA

SEEDING MIXTURE:

PARTRIDGE PEA

SEEDING DATES: Feb 1-May 15

SPECIES
ANNUAL (WINTER) RYE GRASS

SEEDING DATES: Aug 15-Dec 30

50 lb/acre.

- 1. SEE PLANTING & REVEGETATION SPECIFICATIONS FOR MORE INFORMATION
- ON SEED APPLICATION AND ESTABLISHMENT. 2. CONTRACTOR TO KEEP RECORD OF SEED PURCHASE AND APPLICATION
- RATES FOR FINAL INSPECTION (BAGS & RECEIPTS). 3. GROUND STABILIZATION REQUIRED IN (7) SEVEN DAYS ON PERIMETER

AREAS AND SLOPES GREATER THAN 3:1, AND GROUND STABILIZATION IN (14)

A small-stemmed sudangrass may be substituted for Partridge Pea at a rate of

A small-stemmed sudangrass may be substituted for Partridge Pea at a rate of 50 lb/acre.

Follow recommendation of soil tests. Use only amendments safe for riparian areas.

Refertilize if growth is not fully adequate. Topdress with 50 lb/acre of nitrogen in March (if

mixes provided. Reseed, re-fertilize and mulch immediately following erosion or other

applicable). If it is necessary to extend temporary cover beyond June 15th overseed with

RATE (LB/ACRE)

TEMPORARY SEEDING SCHEDULE PERMANENT SEEDING SCHEDULE PERMANENT SEEDING MUST OCCUR WITHIN 14 CALENDAR DAYS OF FINAL GRADING. TEMPORARY SEEDING MUST OCCUR WHEN DENUDED AREAS WILL NOT BE COVER CROPS (TEMPORARY SEEDING) TO BE ADDED TO PERMANENT SEEDING MIXES IF NO BROUGHT TO FINAL GRADE WITHIN 7 CALENDAR DAYS (SEE NOTE 3 ABOVE). TEMPORARY SEEDING HAS BEEN PLACED PREVIOUSLY. SEEDING MIXTURE: PERMANENT SEEDING MIXES: SPECIES
GERMAN MILLET RATE (LB/ACRE) RATE (LB/ACRE) REFERENCE PLANTING PLAN SHEETS 7.1-7.5 FOR PERMANENT SEED MIXES PARTRIDGE PEA A small-stemmed sudangrass may be substituted for Partridge Pea at a rate of 50 The seed mixes above are listed in the specifications and available at ERNST SEEDING DATES: May 15-Aug 15 CONSERVATION SEEDS (800.873.3321). Local sources of similar seed mix may be used (to be approved by Landscape Architect in writing). SEEDING MIXTURE: RATE (LB/ACRE) ANNUAL (WINTER) RYE GRASS

> SOIL AMENDMENTS: Physically or chemically treat all exotic invasive plants before amending soil. Apply lime and fertilizer according to soil tests or apply 4,000 lb/acre ground agricultural limestone and 1,000 lb/acre 5-10-10 fertilizer.

SOIL PREPARATION: Soil impacted by construction must be loosened prior to seeding by means of disking or raking. Seedbed shall be well-pulvarized, loose, and uniform. All stones larger than three (3) inches, sticks, roots, and other extraneous materials shall be removed. Apply seed uniformly with a cyclon seeder, drop-type spreader, drill or hydro-seeder. Cover broadcast seed by lightly raking, then firm surface with roller or cultipacker. Cut or disc temporary seeding cover crop prior to seeding.

If banks exceed 4:1, apply seed, lime, and apply mulch.

Apply 4,000-5,000 lb/acre grain straw or equivalent cover of another suitable, weed-free mulching material. Use a spray-on growth (mulch) matrix (Flexterra FGM or equal) for slope embankments that exceed 3:1

MAINTENANCE: Mow or cut back no more than once a year. Refertilize in the second year unless growth is fully adequate. Reseed, fertilize, and mulch damaged areas immediately. Weed during first 2 years of establishment.


PLAN SYMBOL



**SEEDING SCHEDULE** 

Apply 4,000 lb/acre straw. Anchor straw by tacking.





Suite 206

t 828.253.6856 f 828.253.8256

 $\triangleleft$ 

Copyright © 2021, Equinox Environmental Consultation & Design, Inc.


BID SET

August 21, 2024


AS SHOWN been revised from its original size and the scales noted on drawings/details are no


EROSION CONTROL DETAILS

### SEDIMENT TRAP PLAN VIEW




### SECTION B - B





### SECTION A - A



### MATERIALS

- 1. Use matting made of 100% coconut fiber (coir) twine woven into high strength matrix with the properties shown in Table 6.65a.
- Staples should be made of 0.125 inch diameter new steel wire formed into a 'U' shape not less than 12 inches in length with a throat of 1 inch in width. The staples anchor the porous baffles into the sides and bottom of the basin.
- 3. Ensure that steel posts for porous baffles are of a sufficient height to support baffles at desired height. Posts should be approximately 1-3/8" wide measured parallel to the fence, and have a minimum weight of 1.25 lb/linear ft. The posts must be equipped with an anchor plate having a minimum area of 14.0 square inches and be of the self-fastener angle steel type to have a means of retaining wire and coir fiber mat in the desired position without displacement.
- Use 9-gauge high tension wire for support wire.

basin length. Two (2) coir fiber baffles can be

with a spacing of 1/3 the basin length.

installed in the basins less than 20 ft. in length

### GENERAL NOTES

- 1. SEDIMENT TRAPS SHOULD NOT BE PLACED IN WATERS OF THE STATE OR USGS
- BLUE-LINED STREAMS (UNLESS APPROVED BY FEDERAL AUTHORITIES).

  2. BOTH OUTLET BERM AND THE STONE APRON SHALL HAVE AN UNDERLYING LAYER OF NON-WOVEN GEOTEXTILE FILTER FABRIC.
- 3. ALL INTERNAL SIDE SLOPES OF THE SEDIMENT TRAP SHOULD BE 2.5:1 OR FLATTER.

  4. A SEDIMENT CLEANOUT STAKE SHOULD BE INSTALLED AND MARKED TO REMOVE SEDIMENT
- AT 50% OF THE SEDIMENT STORAGE VOLUME.

  5. AFTER CONSTRUCTION OF EACH SEDIMENT TRAP, THE AREA DISTURBED TO CONSTRUCT
- THE TRAP SHOULD BE PROMPTLY STABILIZED, INCLUDING ALL SIDE SLOPES.

  6. THE FOLLOWING SEDIMENT TRAP REQUIREMENTS SHALL BE MAINTAINED: MAXIMUM EMBANKMENT HEIGHT SHALL BE 5 FEET.
- MAXIMUM RIPRAP OUTLET HEIGHT SHALL BE 3.5 FEET.
  MINIMUM FLOW LENGTH AT TOP OF RIPRAP OUTLET SHALL BE 5 FEET.

INSTALL PER NC DEQ EROSION CONTROL MANUAL.

### INSPECTION AND MAINTENANCE

- THE KEY TO A FUNCTIONAL SEDIMENT TRAP OS WEEKLY INSPECTIONS, ROUTINE MAINTENANCE, AND REGULAR SEDIMENT REMOVAL.
   ATTENTION TO SEDIMENT ACCUMULATIONS WITHIN THE TRAP IS EXTREMELY IMPORTANT.
- ACCUMULATED SEDIMENT DEPOSITION SHOULD BE CONTINUALLY MONITORED IN THE TRAP
- AND REMOVED WHEN NECESSARY. REMOVED ACCUMULATED SEDIMENT WHEN IT REACHES 50% OF THE DESIGNED SEDIMENT
- STORAGE VOLUME AS MARKED BY THE CLEANOUT STAKE.

  4. REMOVED SEDIMENT FROM THE TRAP SHALL BE PLACED IN STOCKPILE STORAGE AREAS OR SPREAD THINLY ACROSS THE DISTURBED AREA. STABILIZE THE REMOVED SEDIMENT IT
- IS RELOCATED.
- 5. REGULAR INSPECTIONS OF SEDIMENT TRAPS SHOULD BE CONDUCTED ONCE EVERY CALENDAR WEEK AND, AS RECOMMENDED, AND WITHIN 24-HOURS AFTER EACH RAINFALL
- EVENT THAT PRODUCES 1/2-INCH OR MORE OF PRECIPITATION
  6. DISTURBED AREAS RESULTING FROM THE REMOVAL OF THE SEDIMENT TRAP SHOULD BE PERMANENTLY STABILIZED AND ADDITIONAL BMP'S, SUCH AS SILT FENCE, SHOULD BE UTILIZED TO HANDLE STORMWATER RUNOFF FROM THIS DISTURBED AREA UNTIL FINAL STABILIZATION IS REACHED.

oir Fiber Baffle Mater	rial Property Requirements
nickness	0.30 in. minimum
ensile Strength (Wet)	900 x 680 lb/ft minimum
ongation (Wet)	69% x 34% maximum
ow Velocity	10-12 ft/sec
eight	20 oz/SY (680 g/m²) minimum
nimum Width	6.5 feet
pen Area	50% maximum

### **BAFFLE INSTAL NOTES:** The percent of surface area for each section of the baffle is as follows:

second cell: 25%

Baffle Material should be secured to the bottom

and sides of basin using 12" landscape staples

 outlet zone: 25% Baffle spacing in future permanent stormwater basins is beyond forebay.

Be sure to construct baffles up the sides of the trap or basin banks so water does not flow around the structures. Most of the sediment will be captured in the inlet zone. Smaller particle size sediments are captured in the latter cells. Be sure to maintain access to the trap for maintenance and sediment removal.

The design life of the fabric is 6-12 months, but may need to be replaced more often if damaged or clogged.

PLAN SYMBOL





14 O'Henry Ave. Suite 206 Asheville, NC 28801 t 828.253.6856 f 828.253.8256



DES	SIGN	BY:	DR	AWN	BY:	CHE	CKED	BY:
DATE								
REVISIONS								

 $\triangleleft$ 

Copyright © 2021, Equinox Environmental Consultation & Design, Inc.

BID SET

August 21, 2024

DRAWING SCALE AS SHOWN NOTE: If this drawing is not 24x36" it has been revised from its original size and the scales noted on drawings/details are no

EROSION CONTROL DETAILS

Inspect	Frequency (during normal	Inspection records must include:
	pusiness nours)	
(1) Rain gauge	Daily	Daily rainfall amounts.
maintained in		If no daily rain gauge observations are made during weekend or
good working		holiday periods, and no individual-day rainfall information is
order		available, record the cumulative rain measurement for those un-
		attended days (and this will determine if a site inspection is
		needed). Days on which no rainfall occurred shall be recorded as
		"zero." The permittee may use another rain-monitoring device
		approved by the Division.
(2) E&SC	At least once per	1. Identification of the measures inspected,
Measures	7 calendar days	
	and within 24	3. Name of the person performing the inspection,
	hours of a rain	
	event > 1.0 inch in	properly,
	24 hours	5. Description of maintenance needs for the measure,
(3) Stormwater	At least once per	-
discharge	7 calendar days	2. Date and time of the inspection,
outfalls (SDOs)	and within 24	
	hours of a rain	
	event ≥ 1.0 inch in	sheen, floating or suspended solids or discoloration,
	24 hours	<ol><li>Indication of visible sediment leaving the site,</li></ol>
		<ol><li>Description, evidence, and date of corrective actions taken.</li></ol>
(4) Perimeter of	At least once per	If visible sedimentation is found outside site limits, then a record
site	7 calendar days	of the following shall be made:
	and within 24	1. Actions taken to clean up or stabilize the sediment that has left
	hours of a rain	
	event ≥ 1.0 inch in	2. Description, evidence, and date of corrective actions taken, and
	24 hours	3. An explanation as to the actions taken to control future
		releases.
(5) Streams or	At least once per	If the stream or wetland has increased visible sedimentation or a
wetlands onsite	7 calendar days	stream has visible increased turbidity from the construction
or offsite	and within 24	activity, then a record of the following shall be made:
(where	hours of a rain	1. Description, evidence and date of corrective actions taken, and
accessible)	event > 1.0 inch in	2. Records of the required reports to the appropriate Division
	24 hours	Regional Office per Part III, Section C, Item (2)(a) of this permit.
(6) Ground	After each phase	<ol> <li>The phase of grading (installation of perimeter E&amp;SC</li> </ol>
stabilization	ofgrading	measures, clearing and grubbing, installation of storm
measures		drainage facilities, completion of all land-disturbing
		activity, construction or redevelopment, permanent
		ground cover).
		<ol><li>Documentation that the required ground stabilization</li></ol>
		measures have been provided within the required
		timeframe or an assurance that they will be provided as

**SECTION C: REPORTING**1. Occurrences that Must be Reported
Permittees shall report the following of
(a) Visible sediment deposition in a str

Oil spills if:
They are 25 gallons or more,
They are less than 25 gallons b
They cause sheen on surface w
They are within 100 feet of sur

nal business nours.  Documentation Requirements	m the of the approved E&SC measure on a copy of the approved E&SC plan or complete, date and sign an inspection report that lists each E&SC measure shown on the approved E&SC plan. This documentation is required upon the initial installation of the E&SC measures or if the E&SC measures or if installation.	pleted. Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate completion of the construction phase.	Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate compliance with approved ground cover specifications.	Complete, date and sign an inspection report.	en Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection
Inspection at all times during normal business nours.  Item to Document Doc	(a) Each E&SC measure has been installed and does not significantly deviate from the locations, dimensions and relative elevations shown on the approved E&SC plan.	(b) A phase of grading has been completed.	(c) Ground cover is located and installed in accordance with the approved E&SC plan.	<ul><li>(d) The maintenance and repair requirements for all E&amp;SC measures have been performed.</li></ul>	(e) Corrective actions have been taken to E&SC measures.

Releases of hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (Ref: 40 CFR 110.3 and 40 CFR 117.3) or Section 102 of CERCLA (Ref: 40 CFR 302.4) or G.S. 143-215.85.

(c)

(p)

2. Additional Documentation to be Kept can addition to the E&SC plan documents site and available for inspectors at all tire Division provides a site-specific exemptithis requirement not practical:

(a) This General Permit as well as the Canada the condess of inspections made during the condess of inspections made during the condess of the condess o

Occurrence
(a) Visible sedime deposition in a stream or wetlan

Reporting Timeframes (After Discovery) and Other Requirements
Within 24 hours, an oral or electronic notification.
Within 7 calendar days, a report that contains a description of the sediment and actions taken to address the cause of the deposition. Division staff may waive the requirement for a written report on a case-by-case basis.
If the stream is named on the NC 303(d) list as impaired for sediment-related causes, the permittee may be required to perform additional monitoring, inspections or apply more stringent practices if staff determine that additional requirements are needed to assure complian with the federal or state impaired-waters conditions.
Within 24 hours, an oral or electronic notification. The notification shall include information about the date, time, nature, volume and location of the spill or release.

Reporting Timeframes and Other Requirements

After a permittee becomes aware of an occurrence that must be reported, he shall the appropriate Division regional office within the timeframes and in accordance wother requirements listed below. Occurrences outside normal business hours may reported to the Department's Environmental Emergency Center personnel at (800) 858-0368.

ee Vears I all inspection records shall be maintained for a pe and made available upon request. [40 CFR 122.41]

### SECTION G, ITEM (4) ASINS FOR MAINTENANCE OR CLOSE OUT

A report at least ten days before the date of the bypass, if possible.
The report shall include an evaluation of the anticipated quality and effect of the bypass.
Within 24 hours, an oral or electronic notification.
Within 24 hours, and or electronic notification of the noncompliance is expected to continue; and steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance. [40 CFR 122.41()](6).
Division staff may waive the requirement for a written report on a case-by-case basis.

n (2)(c) and (d) of this oved from the sedim ction C, Ite r that is ren (p)

# NCG01 SELF-INSPECTION, RECORDKEEPING AND REPORTING

EFFECTIVE: 04/01/19

DNSITE CONCRETE STRUCTURE WITH

NORTH CAROLINA Environmental Quality

# GROUND STABILIZATION AND MATERIALS HANDLING PRACTICES FOR COMPLIANCE WITH THE NCGO1 CONSTRUCTION GENERAL PERMIT Implementing the details and specifications on this plan sheet will result in the construction activity being considered compliant with the Ground Stabilization and Materials Handling sections of the NCG01 Construction General Permit (Sections E and F, respectively). The permittee shall comply with the Erosion and Sediment Control plan approved by the delegated authority having jurisdiction. All details and specifications shown on this sheet may not apply depending on site conditions and the delegated authority having invidations.

	IZATION	Required Ground Stabilization Timeframes	Stabilize within this	many calendar Timeframe variations days after ceasing land disturbance	7 None	7 None	If slopes are 10' or less in length and are 7 not steeper than 2:1, 14 days are allowed	-7 days for slopes greater than 50' in length and with slopes steeper than 4:1 -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed	-7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed unless there is zero slope	lote: After the permanent cessation of construction activities, any areas with temporary
	ABILIZATION Required Group	Required Groun	Stabilize witl			7	n 7	14	14	ent cessation of c
ECTION E: GROUND STABILIZATION Required Gro				Site Area Description	Perimeter dikes, swales, ditches, and perimeter slopes	<ul><li>(b) High Quality Water (HQW) Zones</li></ul>	Slopes steeper than 3:1	(d) Slopes 3:1 to 4:1	Areas with slopes flatter than 4:1	: After the permane
	낊			S	(a)	(q)	(c)	(p)	(e)	ಠ

stabilization shall be converted to permanent ground stabilization as soon as sole but in no case longer than 90 calendar days after the last land disturbing. Temporary ground stabilization shall be maintained in a manner to render th stable against accelerated erosion until permanent ground stabilization is achi

ID STABILIZATION SPECIFICATION

E the ground sufficiently so that rain will not dislodge the soil. Use one of the ues in the table below:

NCG0

- Maintain vehicles and equipment to prevent discharge of fluids.
   Provide drip pans under any stored equipment.
   Identify leaks and repair as soon as feasible, or remove leaking equipn project.
   Collect all spent fluids, store in separate containers and properly dispont azardous waste (recycle when possible).
   Remove leaking vehicles and construction equipment from service unhas been corrected.
   Bring used fuels, lubricants, coolants, hydraulic fluids and other petrol to a recycling or disposal center that handles these materials.
- e as the tainers and properly di

- Inter, Building Material And Land Clearing waste
   Never bury or burn waste. Place litter and debris in approved waste container
   Provide a sufficient number and size of waste containers (e.g dumpster, trash receptacle) on site to contain construction and domestic wastes.
   Locate waste containers at least 50 feet away from storm drain inlets and surfawaters unless no other alternatives are reasonably available.
   Locate waste containers on areas that do not receive substantial amounts of refrom upland areas and does not drain directly to a storm drain, stream or weth from upland areas and does not drain directly to a storm drain, stream or weth provide secondary containment. Repair or replace damaged waste containers.
   Anchor all lightweight items in waste containers during times of high winds.
   Empty waste containers as needed to prevent overflow. Clean up immediately containers overflow.
   Dispose waste off-site at an approved disposal facility.
   On business days, clean up and dispose of waste in designated waste container.

ONCRETE WASHOUTS

1. Do not discharge concrete or cement slurry from the site.
2. Dispose of, or recycle settled, hardened concrete residue in accordance with local and state solid waste regulations and at an approved facility.
3. Manage washout from mortar mixers in accordance with the above item and in addition place the mixer and associated materials on impervious barrier and within lot perimeter silt fence.
4. Install temporary concrete washouts per local requirements, where applicable. If a alternate method or product is to be used, contact your approval authority for review and approval. If local standard details are not available, use one of the two types of temporary concrete washouts provided on this detail.
5. Do not use concrete washouts for dewatering or storing defective curb or sidewalk sections. Stormwater accumulated within the washout may not be pumped into or discharged to the storm drain system or receiving surface waters. Liquid waste mube pumped out and removed from storm drain inlets and surface waters unless can be shown that no other alternatives are reasonably available. At a minimum, install protection of storm drain inlet(s) closest to the washout which could receive spills or overflow.

e above item and in ious barrier and with

- quid waste into storm drains, streams or wetlanc 50 feet away from storm drain inlets and surface tives are reasonably available. rolled area.

Spills or overflow.
Locate washouts in an easily accessible area, on level ground and install a stone entrance pad in front of the washout. Additional controls may be required by the approving authority.
Install at least one sign directing concrete trucks to the washout within the project limits. Post signage on the washout itself to identify this location.
Remove leavings from the washout when at approximately 75% capacity to limit overflow events. Replace the tarp, sand bags or other temporary structural components when no longer functional. When utilizing alternative or proprietary products, follow manufacturer's instructions.
At the completion of the concrete work, remove remaining leavings and dispose of in an approved disposal facility. Fill pit, if applicable, and stabilize any disturbance caused by removal of washout.

## ns. Locate earthen-material stockpile areas at least nlets, sediment basins, perimeter sediment controls be shown no other alternatives are reasonably

ides and rodenticides in their original containers with ons for use, ingredients and first aid steps in case of

RBICIDES, PESTICIDES AND RODENTICIDES

Store and apply herbicides, pesticides and rodenti restrictions.

Store herbicides, pesticides and rodenticides in the label, which lists directions for use, ingredients an accidental poisoning.

Do not store herbicides, pesticides and rodenticide possible or where they may spill or leak into wells, or surface water. If a spill occurs, clean area imme.

Do not stockpile these materials onsite.

- nt when feasible.

  neframes provided on this sheet and in accordance
  additional requirements. Soil stabilization is defined
  cal coverage techniques that will restrain accelerated
  mporary or permanent control needs.




04/01/1

EFFECTIVE:

HAZARDOUS AND TOXIC WASTE

1. Create designated hazardous waste collection
2. Place hazardous waste containers under cover
3. Do not store hazardous chemicals, drums or ba

HANDLING AND MATERIALS TABILIZ GROUND



 $\triangleleft$ 


 $\mathrel{\begin{array}{c} - \\ \hline \end{array}}$ 

Copyright © 2021, Equinox Environmental Consultation & Design, Inc.

BID SET

August 21, 2024

s Rd. 28789




CA POLITICA NOSCA NATIONAL PROPERTY OF THE PRO DESIGN BY: DRAWN BY: CHECKED E

EQUINOX


14 O'Henry Ave.
Suite 206
Asheville, NC 28801
t 828.253.6856
f 828.253.8256

AS SHOWN NOTE: If this drawing is not 24x36" it has been revised from its original size and the scales noted on drawings/details are no EROSION CONTROL NOTES




- 1. ALL PAVING WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH THE NC DOT STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES.
- 2. ALL ASPHALT PAVEMENT AND BASE COURSE THICKNESS SPECIFIED SHALL BE AFTER
- COMPACTION. 3. SUBGRADE AND BASE COURSE SHALL BE MECHANICALLY COMPACTED (ROLLED) IN ACCORDANCE WITH ASTM D698).
- 4. POSITIVE DRAINAGE IS REQUIRED FOR ALL FINISHED GRADES OF BASE COURSES AND SURFACE
- COURSES TO ENSURE PROPER DRAINAGE AND NO SETTLING OCCURS (MIN.1%).






- CONCRETE TO BE  $\frac{1}{2}$ " TO  $\frac{3}{4}$ " ABOVE THE GRADE IF ADJACENT TO A VEGETATED SURFACE AND FLUSH WITH
- HARD SURFACE TO ACHIEVE POSITIVE DRAINAGE.
- 2. PLACE A  $\frac{1}{8}$ " SAW CUT CONTROL JOINT AS SHOWN ON PLAN TO 1  $\frac{1}{2}$ " DEPTH. PLACE A  $\frac{1}{8}$ " EXPANSION JOINT AT EVERY MATERIAL CHANGE.
- 4. FINISH PËR MATERIALS PLAN, SHEET L4.1/2/3.






### NOTES:


- 1. ALL PAVING WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH THE NC DOT STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES.
- 2. ALL ASPHALT PAVEMENT AND BASE COURSE THICKNESS SPECIFIED SHALL BE AFTER
- COMPACTION.
- 3. SUBGRADE AND BASE COURSE SHALL BE MECHANICALLY COMPACTED (ROLLED) IN ACCORDANCE WITH ASTM D698).
- 4. POSITIVE DRAINAGE IS REQUIRED FOR ALL FINISHED GRADES OF BASE COURSES AND SURFACE COURSES TO ENSURE PROPER DRAINAGE AND NO SETTLING OCCURS (MIN.1%).






- 1. CONCRETE TO BE 1/2" TO 3/4" ABOVE THE GRADE IF ADJACENT TO VEGETATED SURFACE AND FLUSH WITH HARD SURFACE TO ACHIEVE POSITIVE DRAINAGE.
- 2. PLACE A 1/8" SAW CUT CONTROL JOINT AS SHOWN ON PLAN TO 1 1/2" DEPTH.
- 3. PLACE A 1/8" EXPANSION JOINT AT EVERY MATERIAL CHANGE.
- 4. FINISH PER MATERIALS PLAN, SHEET L4.1/2/3.






### NOTES:

- 1. SURFACE TO BE  $\frac{1}{2}$ " TO  $\frac{3}{4}$ " ABOVE THE GRADE IF ADJACENT TO VEGETATED SURFACE
- AND FLUSH WITH HARD SURFACE TO ACHIEVE POSITIVE DRAINAGE.
- 2. PLACE A 1/8" EXPANSION JOINT AS RECOMMENDED BY MANUFACTURER.












1. WITHIN FALL ZONES, MULCH DEPTH TO BE 9" MINIMUM.






FLUSH CONCRETE CURB



CONCRETE CURB



NATURAL SURFACE TRAIL - REINFORCED

1. FOR MEANS OF CONSTRUCTION AND CROSS SLOPE, SEE NATURAL SURFACE TRAIL DETAILS (1, 2/L8.1) 2. FOR EXTENTS, SEE LAYOUT PLAN, SHEET L3.1.

Copyright © 2021, Equinox Environmental Consultation & Design, Inc. BID SET August 21, 2024 DRAWING SCALE AS SHOWN been revised from its original size and the scales noted on drawings/details are no PAVING DETAILS


 $\triangleleft$ 


 $\exists$ 

14 O'Henry Ave. Suite 206 Asheville, NC 28801

DESIGN BY: DRAWN BY: CHECKED B


t 828.253.6856 f 828.253.8256






- 1. THE TRAIL SHALL BE ALIGNED TO AVOID REMOVAL OF TREES GREATER THAN 6" IN DIAMETER
- FOOTPRINT NO WIDER THAN THE SPECIFIED TRAIL TREAD UNLESS APPROVED BY THE PROJECT
- UNLESS OTHERWISE SPECIFIED, THE TRAIL SHALL BE CONSTRUCTED WITH A "FULL BENCH CUT".
- 7. THE TRAIL SHALL HAVE A COMPACTED SOIL SURFACE. COMPACTION SHALL BE COMPLETED USING A MECHANIZED TAMPER SUCH AS A VIBRATING PLATE COMPACTOR. THE TRAIL SHALL BE SHAPED TO LEAVE A UNIFORM SURFACE FREE FROM INDENTATIONS OR PROTRUSIONS. THE GRADING OF THE TREAD, BACK SLOPE, AND DRAINAGE FEATURES SHALL BE FINISHED TO A SMOOTH, STABLE
- 8. TRAILS CONSTRUCTED WITHIN 100FT OF A STREAM SHALL BE COMPLETED AND STABALIZED BY THE END OF EACH WORK DAY.
- GRADE REVERSALS AND GRADE DIPS SHALL BE CONSTRUCTED EVERY 20 TO 50-FEET TO REMOVE WATER FROM THE TRAIL TREAD. ALL NEEDED GRADE REVERSALS AND/OR DIPS WILL BE DONE
- ACCORDING TO IMBA STANDARDS AS SPECIFIED IN THEIR BOOK TRAIL SOLUTIONS. 10. LONGITUDINAL GRADES SHALL NOT EXCEED 10%.

### <u>SECTION</u>





INCLUDE PARK NAME AND LOGOS OF PERTINENT ENTITIES. LOWER SIGN TO INCLUDE PARK HOURS.

NATURAL SURFACE TRAIL CONSTRUCTION

2 \ PARK SIGN

INFILTRATION TRENCH \L8.1

DESIGN BY: DRAWN BY: CHECKED B Copyright © 2021, Equinox Environmental Consultation & Design, Inc. BID SET August 21, 2024


BREAST HEIGHT WHERE POSSIBLE. STUMPS LOCATED IN THE TRAIL TREAD SHALL BE COMPLETELY REMOVED. THOSE LOCATED IN THE TRAIL CORRIDOR TO BE CUT FLUSH TO THE GROUND. 3. WORK SHALL BE PERFORMED WITH HAND TOOLS OR LOW IMPACT MECHANIZED EQUIPMENT WITH A THE TRAIL BACKSLOPE SHALL TRANSITION SMOOTHLY TO THE BERMSIDE. ALL VEGETATIVE/ROOT MATTER, WITH THE EXCEPTION OF LARGE FEEDER ROOTS, AND ROCKS IN THE TRAIL TREAD SHALL BE REMOVED; AND HOLES SHALL BE FILLED WITH SUITABLE MATERIAL AND COMPACTED.


14 O'Henry Ave. Suite 206 Asheville, NC 28801


t 828.253.6856 f 828.253.8256

DRAWING SCALE AS SHOWN been revised from its original size and the scales noted on drawings/details are no longer applicable.

PARK SIGN & TRAIL DETAILS














Copyright © 2021, Equinox Environmental Consultation & Design, Inc.


BID SET

August 21, 2024

DRAWING SCALE AS SHOWN


NOTE: If this drawing is not 24x36" it has been revised from its original size and the scales noted on drawings/details are no longer applicable.

PARKING & **ACCESSIBILITY** DETAILS









Jackson County

QUALLA WHITTIER

Sunset Farms Rd.
Whittier, NC 28789

Copyright © 2021, Equinox Environmental Consultation & Design, Inc. HASE

BID SET

August 21, 2024

DRAWING SCALE

AS SHOWN


AS SHOWN


NOTE: If this drawing is not 24x36" it has been revised from its original size and the scales noted on drawings/details are no longer applicable.


RAWING NAME

STORMWATER DETAILS

L8.5







C6051

DocuSign Envelope ID: EDCEEE38-AAFB-4922-9AF6-3DFF01ACE310

QUALLA WHITTIER PA

INITIAL PLAN DATE: 6/17/2024

REVISIONS:

DRN: WR DGN: WR CKD: WR

DETAILS